


**CITY OF HANFORD  
PRE-REVIEWED  
ACCESSORY DWELLING UNIT PROGRAM**



**375 SQ. FT.  
STUDIO 1 BATH  
ACCESSORY DWELLING UNIT  
DETACHED**

These plans and documents have been reviewed for compliance with the applicable codes requirements of the jurisdiction. The stamping of these plans shall not be held to permit or be an approval of any violation of applicable codes and standards nor relieve the owner, design professional of record or contractor of compliance with applicable codes and standards

ROD CARSEY CONSULTING & PLAN CHECK  
SERVICE 11/8/2024

**MASTER PLAN DESIGN**

**ADU375**

**2022 CBC LOCK UNDER HSC 18938.5(d)(AB130)**

**APPROVAL DATE: 12/11/2025**

**EXPIRES: 12/11/2035**

**10 YEAR LOCK IS NOT APPLICABLE TO THE CALIFORNIA ENERGY CODE, PV REQUIREMENTS, OR CALGREEN AND LANDSCAPE WATER-EFFICIENCY STANDARDS**

**CITY OF HANFORD BUILDING DIVISION  
APPROVED**

**THIS SET OF PLANS AND SPECIFICATIONS  
MUST BE KEPT ON THE JOB AT ALL TIMES AND  
NO CHANGES OR ALTERATIONS SHALL BE  
MADE EXCEPT BY THE BUILDING DIVISION.**

**THE STAMPING OF THIS PLAN AND  
SPECIFICATIONS SHALL NOT BE HELD TO  
PERMIT OR TO BE AN APPROVAL OF THE  
VIOLATION OF ANY PROVISIONS OF ANY CITY  
ORDINANCE OR STATE LAW. "REVIEWED FOR  
CODE COMPLIANCE."**

**BY: Mitchell Coach  
12/11/2025**

**DISCLAIMER:  
BY USING THESE STANDARD PLANS, THE USER AGREES TO  
RELEASE THE CITY OF HANFORD FROM ANY AND ALL CLAIMS,  
LIABILITIES, SUITS AND DEMANDS ON ACCOUNT OF ANY  
INJURY, DAMAGE, OR LOSS TO PERSONS OR PROPERTY,  
OUT OF THE USE OF THESE PLANS, ARISING  
OUT OF THE USE OF THESE PLANS, OR CONSTRUCTION DOCUMENTS, THE  
USE OF THESE PLANS DOES NOT ELIMINATE OR REDUCE THE  
USER'S RESPONSIBILITY TO VERIFY ANY AND ALL INFORMATION.**

<b>SHEET INDEX</b>	
<b>COVER SHEETS</b>	
C0	COVER SHEET
C1	COVER SHEET 1
C2	COVER SHEET 2
<b>ARCHITECTURAL SHEETS</b>	
A1	FLOOR PLAN
A2	SECTIONS
A3	ELEVATION A
A4	ELEVATION B
A5	ELEVATION C
A6	ARCHITECTURAL DETAILS
<b>STRUCTURAL SHEETS</b>	
S1	FOUNDATION PLAN
S2	ROOF FRAMING PLAN
S3	DETAIL SHEET 1
S4	DETAIL SHEET 2
<b>ELECTRICAL SHEETS</b>	
E1	ELECTRICAL PLAN
<b>PLUMBING SHEETS</b>	
P1	PLUMBING PLAN
<b>CALGREEN FORMS</b>	
G1	CALGREEN FORM 1
G2	CALGREEN FORM 2
<b>MECHANICAL SHEETS</b>	
M1	HVAC PLAN
<b>ENERGY COMPLIANCE SHEET</b>	
EN1	ENERGY COMPLIANCE

**ADU INFO**

OCCUPANCY TYPE R-3  
CONSTRUCTION TYPE VB  
CLIMATE ZONE 13

**ADDITIONAL REQUIREMENTS DUE AT TIME OF SUBMITTAL**

TRUSS DRAWINGS AND ANALYSIS

FIRE SPRINKLER PLAN - **if applicable**

SOLAR PHOTOVOLTAIC (PV) PLAN

GEOTECHNICAL SOILS AND FOUNDATION INVESTIGATION

**Current CalGreen Forms - if submitted after 12/31/2025**

**Current Energy Compliance Sheets - if submitted after 12/31/2025**

**BUILDING CODE:**

2022 BUILDING STANDARDS ADMINISTRATIVE CODE, PART 1, TITLE 24 C.C.R.

2022 CALIFORNIA RESIDENTIAL CODE (CRC) PART 2, TITLE 24 PART 2.5 (2021 INTERNATIONAL BUILDING CODE WITH CALIFORNIA AMENDMENTS).

2022 CALIFORNIA ELECTRICAL CODE (CEC), PART 3, TITLE 24 C.C.R. (2020 NATIONAL ELECTRICAL CODE OF THE NATIONAL FIRE PROTECTION ASSOCIATION)

2022 CALIFORNIA MECHANICAL CODE (CMC), PART 4, TITLE 24 C.C.R. (2021 UNIFORM MECHANICAL CODE AND CA AMENDMENTS)

2022 CALIFORNIA PLUMBING CODE (CPC), PART 5, TITLE 24 C.C.R. (2020 UNIFORM PLUMBING CODE AND AMENDMENTS)

2022 CALIFORNIA ENERGY CODE AND ENERGY COMMISSION STANDARDS (CECS), PART 6, TITLE 24 C.C.R.

2022 CALIFORNIA FIRE CODE (CFC), PART 9, TITLE 24 C.C.R. (2021 INTERNATIONAL FIRE CODE)

2022 CALIFORNIA GREEN BUILDING STANDARDS CODE, PART 11 TITLE 24 C.C.R.

2022 CALIFORNIA REFERENCED STANDARDS CODE, PART 12 TITLE 24 C.C.R.

2022 TITLE 19 C.C.R. PUBLIC SAFETY, STATE FIRE MARSHAL

CONTRACTOR SHALL REFER TO THE ABOVE CITED CODES AND LOCAL REGULATIONS WHERE SPECIFIC DETAILS ARE REQUIRED BUT NOT DEPICTED IN THE APPROVED PLANS.



PROJECT TITLE	CITY OF HANFORD - PRE-REVIEWED ADU PROGRAM	
ADU SQFT	375	
SHEET DESCRIPTION	COVER	DATE
AGENCY	SJV REAP	10/28/2024
DRAWING SCALE	---	
SHEET	C0	

<p><b>A. GENERAL</b></p> <p>1. NOTES AND DETAILS ON THE DRAWINGS SHALL TAKE PRECEDENCE OVER THESE NOTES. THE DETAILS ON THE DRAWINGS SHALL APPLY IN ALL CASES UNLESS SPECIFICALLY SHOWN OTHERWISE, WHERE CONDITIONS ARE NOT SPECIFICALLY INDICATED, DETAILS OF A CHARACTER SIMILAR TO THOSE SHOWN SHALL BE USED, SUBJECT TO REVIEW.</p> <p><b>B. ELECTRICAL, PLUMBING, AND MECHANICAL</b></p> <p>1. EXTERIOR LIGHTING. ALL PROJECTS SHALL COMPLY WITH THE RESPECTIVE CITY'S MUNICIPAL CODE.</p> <p>2. DETECTORS. ALL DETECTORS MUST BE HARD WIRED TO THE BUILDING'S ELECTRICAL SYSTEM, INSTALLED PER THE MANUFACTURER'S INSTALLATION INSTRUCTIONS AND SHALL BE INTERCONNECTED, WITH BATTERY BACKUP [CRC R314.1]</p> <p>2.1. SMOKE DETECTORS. SMOKE DETECTORS ARE REQUIRED IN EACH EXISTING SLEEPING ROOM, OUTSIDE EACH SEPARATE SLEEPING AREA IN THE IMMEDIATE VICINITY OF SLEEPING ROOMS, AND ON EACH STORY OF A DWELLING INCLUDING BASEMENTS. (CRC R314.3)</p> <p>2.2. CARBON MONOXIDE DETECTORS. CARBON MONOXIDE DETECTORS ARE REQUIRED OUTSIDE EACH SEPARATE SLEEPING AREA IN THE IMMEDIATE VICINITY OF SLEEPING ROOMS AND ON EACH STORY OF A DWELLING INCLUDING BASEMENTS. (CRC R315.3)</p> <p>3. WATER HEATER SEISMIC STRAPPING. MINIMUM TWO 3/4-INCH-BY-24-GAUGE STRAPS REQUIRED AROUND WATER HEATERS, WITH 1/4-INCH-BY-3-INCH LAG BOLTS ATTACHED DIRECTLY TO FRAMING. STRAPS SHALL BE AT POINTS WITHIN UPPER THIRD AND LOWER THIRD OF WATER HEATER VERTICAL DIMENSION. LOWER CONNECTION SHALL OCCUR MINIMUM 4 INCHES ABOVE CONTROLS. (CPC 507.2)</p> <p>4. WATER CLOSET CLEARANCE. MINIMUM 30-INCH-WIDE BY 24-INCH-DEEP CLEARANCE REQUIRED AT FRONT OF WATER CLOSETS. (CPC 402.5)</p> <p>5. SHOWER SIZE. SHOWER COMPARTMENTS SHALL HAVE MINIMUM AREA OF 1024 SQUARE INCHES AND BE ABLE TO ENCOMPASS A 30-INCH-DIAMETER CIRCLE. SHOWER DOORS SHALL HAVE A MINIMUM 22-INCH UNOBSTRUCTED WIDTH. (CPC 408.5 AND CPC 408.6)</p> <p><b>C. MECHANICAL VENTILATION AND INDOOR AIR QUALITY (ASHRAE 62.2-2010)</b></p> <p>1. TRANSFER AIR. VENTILATION AIR SHALL BE PROVIDED DIRECTLY FROM THE OUTDOORS AND NOT AS TRANSFER AIR FROM ADJACENT DWELLING UNITS OR OTHER SPACES, SUCH AS GARAGES, UNCONDITIONED CRAWLSPACES, OR UNCONDITIONED ATTICS. (CBEES 150.0(O))</p> <p>2. INSTRUCTIONS AND LABELING. VENTILATION SYSTEM CONTROLS SHALL BE LABELED AND THE HOME OWNER SHALL BE PROVIDED WITH INSTRUCTIONS ON HOW TO OPERATE THE SYSTEM. (CBEES 150.0(O))</p> <p>3. COMBUSTION AND SOLID-FUEL BURNING APPLIANCES. COMBUSTION APPLIANCES SHALL BE PROPERLY VENTED AND AIR SYSTEMS SHALL BE DESIGNED TO PREVENT BACK DRAFTING. (CBEES 150.0(O))</p> <p>4. MINIMUM FILTRATION. MECHANICAL SYSTEMS SUPPLYING AIR TO OCCUPYABLE SPACE THROUGH DUCTWORK SHALL BE PROVIDED WITH A FILTER HAVING A MINIMUM EFFICIENCY OF MERV 13 OR BETTER. (CBEES 150.0(O))</p> <p>5. AIR INLETS. AIR INLETS (NOT EXHAUST) SHALL BE LOCATED AWAY FROM KNOWN CONTAMINANTS. (CBEES 150.0(O))</p> <p>6. AIR MOVING EQUIPMENT. AIR MOVING EQUIPMENT USED TO MEET EITHER THE WHOLE-BUILDING VENTILATION REQUIREMENT OR THE LOCAL VENTILATION EXHAUST REQUIREMENT SHALL BE RATED IN TERMS OF AIRFLOW AND SOUND. (CBEES 150.0(O))</p> <p>6.1. ALL CONTINUOUSLY OPERATING FANS SHALL BE RATED AT A MAXIMUM OF 1.0 SONE.</p> <p>6.2. INTERMITTENTLY OPERATED WHOLE-BUILDING VENTILATION FANS SHALL BE RATED AT A MAXIMUM OF 1.0 SONE.</p> <p>6.3. INTERMITTENTLY OPERATED LOCAL EXHAUST FANS SHALL BE RATED AT MAXIMUM OF 3.0 SONE.</p> <p>6.4. REMOTELY LOCATED AIR-MOVING EQUIPMENT (MOUNTED OUTSIDE OF HABITABLE SPACES) NEED NOT MEET SOUND REQUIREMENTS IF AT LEAST 4 FEET OF DUCTWORK BETWEEN FAN AND INTAKE GRILL.</p> <p>7. LOCAL EXHAUST FANS TO EXTERIOR TO PROVIDE MINIMUM 50 CFM INTERMITTENT OR 20 CFM CONTINUOUS VENTILATION OR AS SPECIFIED IN ENERGY REPORT.</p> <p>8. AN INTERMITTENTLY OR CONTINUOUSLY OPERATING LOCAL MECHANICAL EXHAUST VENTILATION SYSTEM SHALL BE INSTALLED IN EACH BATHROOM WITH A BATHTUB, SHOWER, OR SIMILAR MOISTURE SOURCE AND IN EACH KITCHEN IN COMPLIANCE WITH ASHRAE STANDARD 62.2 AS ADOPTED BY THE CALIFORNIA ENERGY COMMISSION.</p> <p>8.1. BATHROOMS: INTERMITTENT LOCAL EXHAUST VENTILATION AIRFLOW RATES SHALL NOT BE LESS THAN 50 CFM. CONTINUOUS OPERATION SHALL NOT BE LESS THAN 20 CFM. (CMC 405.3.1)</p> <p>8.2. KITCHENS: INTERMITTENT CONTROLLED OPERATIONS, THE EXHAUST RATE SHALL NOT BE LESS THAN 100 CFM FOR RANGE HOODS OR 300 CFM FOR MECHANICAL EXHAUST FANS INCLUDING DOWNDRAFT APPLIANCES. CONTINUOUS OPERATED VENTILATION, THE EXHAUST RATE SHALL NOT BE LESS THAN 5CFM OR 4% OF THE OCCUPIED FLOOR AREA. (CMC 405.4.1)</p> <p><b>D. FOUNDATION</b></p> <p>1. PROJECTS DETERMINED TO BE IN SEISMIC DESIGN CATEGORY (SDC) "D" REQUIRE A GEOTECHNICAL SOILS AND FOUNDATION INVESTIGATION [CBC 1803.2 &amp; 1803.5.12] UNLESS WAIVED BY THE BUILDING OFFICIAL. THE SOILS ENGINEER SHALL BE RESPONSIBLE FOR REVIEWING AND COORDINATING THE SITE PLAN AND THE FOUNDATION PLAN PREPARED BY OTHERS FOR CONFORMITY WITH THE RECOMMENDATIONS OF HIS SOILS REPORT AND SHALL SIGNIFY HIS REVIEW BY CERTIFYING THE FIRST SHEET OF SAID PLANS [CRC R301.1.3.1].</p> <p>1.1. SAMPLE CERTIFICATION.</p> <p>THESE PLANS CONFORM TO THE GEOTECHNICAL REPORT # _____ DATED _____ AS PREPARED UNDER MY SUPERVISION. WE MAKE NO REPRESENTATION AS TO THE ACCURACY OF DIMENSIONS, MEASUREMENTS, CALCULATIONS OR ANY PORTION OF THE DESIGN.</p> <p>2. FOUNDATION REINFORCEMENT. CONTINUOUS FOOTINGS AND STEM WALLS SHALL BE PROVIDED WITH A MINIMUM TWO LONGITUDINAL NO. 4 BARS, ONE AT THE TOP AND ONE AT THE BOTTOM OF THE FOOTING. (CRC R403.1.3.3)</p> <p>3. INTERIOR BRACED WALL FOUNDATION SUPPORT. BRACED WALLS SHALL BE SUPPORTED BY CONTINUOUS FOUNDATIONS. (CRC 403.1.3.4)</p> <p>4. HORIZONTAL REINFORCEMENT SHALL BE THE LONGEST LENGTHS PRACTICAL. WHERE SPLICES ARE NECESSARY IN REINFORCEMENT, THE LENGTH OF LAP SPLICE SHALL BE 40 BAR DIAMETERS. THE MAXIMUM GAP BETWEEN NONCONTACT PARALLEL BARS AT A LAP SPLICE SHALL NOT EXCEED THE SMALLER OF ONE-FIFTH THE REQUIRED LAP LENGTH AND 6 INCHES [SEE FIGURE R608.5.4(1)]</p> <p>5. ANCHOR BOLTS AND SILLS. FOUNDATION PLATES OR SILLS SHALL BE BOLTED OR ANCHORED TO THE FOUNDATION OR FOUNDATION WALL PER THE FOLLOWING (CRC R403.1.6 AND CRC R602.11.1):</p> <p>5.1. MINIMUM 1/2-INCH-DIAMETER STEEL BOLTS, ASTM F1554, GR36</p> <p>5.2. BOLTS EMBEDDED AT LEAST 7 INCHES INTO CONCRETE OR MASONRY</p> <p>5.3. THE BOLTS SHALL BE LOCATED IN THE MIDDLE THIRD OF THE WIDTH OF THE PLATE.</p> <p>5.4. MINIMUM TWO BOLTS PER PLATE/SILL PIECE WITH ONE BOLT LOCATED MAXIMUM 12 INCHES AND MINIMUM 7 BOLT DIAMETERS FROM EACH END OF EACH SILL PLATE/PIECE</p> <p>5.5. MINIMUM 3-INCH BY 3-INCH BY 0.229-INCH STEEL PLATE WASHER BETWEEN SILL AND NUT ON EACH BOLT EXCEPT WHERE APPROVED ANCHOR STRAPS ARE USED. THE HOLE IN THE PLATE WASHER IS PERMITTED TO BE DIAGONALLY SLOTTED WITH A WIDTH OF UP TO <math>\frac{1}{8}</math> INCH LARGER THAN THE BOLT DIAMETER AND A SLOT LENGTH NOT TO EXCEED 1-3/4 INCHES, PROVIDED STANDARD CUT WASHER IS PLACED BETWEEN THE PLATE WASHER AND THE NUT.</p> <p>6. HOLD-DOWNS. ALL HOLD-DOWNS MUST BE TIED IN PLACE PRIOR TO FOUNDATION INSPECTION.</p> <p>7. FASTENERS FOR PRESSURE-PRESERVATIVE TREATED AND FIRE RETARDANT TREATED WOOD SHALL BE HOT-DIPPED ZINC COATED GALVANIZED, STAINLESS STEEL OR COPPER (CRC R317.3)</p> <p>8. VAPOR RETARDER.</p> <p>8.1. A VAPOR RETARDER INSPECTION WILL BE REQUIRED PRIOR TO PLACEMENT OF THE SAND TO CONFIRM PROPER INSTALLATION (VAPOR RETARDER IS TO BE ASTM E1745 CLASS A COMPLIANT AND MANUFACTURER'S INSTALLATION REQUIREMENTS MUST BE AVAILABLE FOR INSPECTION PURPOSES).</p> <p>8.2. A MINIMUM 10-MIL VAPOR RETARDER CONFORMING TO ASTM E1745 CLASS A REQUIREMENTS WITH JOINTS LAPPED NOT LESS THAN 6' IS REQUIRED.</p> <p>8.3. PROVIDE 4" NOMINAL THICK CONCRETE SLAB WITH #3 REBAR AT 24" O.C. EACH WAY, PLACED MID-HEIGHT OF SLAB OVER 2" SAND BLOTTER INSTALLED OVER 10 MIL VAPOR RETARDER CONFORMING TO ASTM E1745 OVER AN ADDITIONAL 2" SAND OVER COMPAKTED FILL COMPLYING WITH SITE SOILS REPORT.</p> <p><b>E. WOOD FRAMING</b></p> <p>1. FASTENER REQUIREMENTS. THE NUMBER, SIZE, AND SPACING OF FASTENERS CONNECTING WOOD MEMBERS/ELEMENTS SHALL NOT BE LESS THAN THAT SET FORTH IN CRC TABLE R602.3(1). (CRC R602.3)</p> <p>2. SILL PLATE. STUDS SHALL HAVE FULL BEARING ON NOMINAL 2-INCH THICK OR LARGER SILL PLATE WITH WIDTH AT LEAST EQUAL TO STUD WIDTH. (CRC R602.3.4)</p> <p>3. BEARING STUDS. WHERE JOISTS, TRUSSES, OR RAFTERS ARE SPACED MORE THAN 16 INCHES ON CENTER AND THE BEARING STUDS BELOW ARE SPACED 24 INCHES ON CENTER, SUCH MEMBERS SHALL BEAR WITHIN 5 INCHES OF THE STUDS BEHIND. (CRC R602.3.3) EXCEPTION: THE TOP PLATES ARE TWO 2-INCH BY 6-INCH OR TWO 3-INCH BY 4- INCH MEMBERS.</p> <p><b>F. BASIS OF DESIGN</b></p> <p>NOTE: WINTER DESIGN TEMP, FLOOD HAZARDS, AIR FREEZING INDEX AND MEAN ANNUAL TEMP SECTIONS ARE REQUIRED BY APPLICANT AT TIME OF SUBMITTAL.</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th rowspan="2">GROUND SNOW LOAD</th> <th colspan="2">WIND DESIGN</th> <th rowspan="2">SEISMIC DESIGN CAT</th> <th colspan="3">SUBJECT TO DAMAGE FROM</th> <th rowspan="2">Winter Design Temp</th> <th rowspan="2">ICE BARRIER UNDERCAYMENT REQUIRED</th> <th rowspan="2">FLOOD HAZARDS</th> <th rowspan="2">AIR FREEZING INDEX</th> <th rowspan="2">MEAN ANNUAL TEMP</th> </tr> <tr> <th>Speed (mph)</th> <th>Topographic effects</th> <th>Weathering</th> <th>Frost Line Depth</th> <th>Termitic</th> </tr> </thead> <tbody> <tr> <td>0</td> <td>110</td> <td>NO</td> <td>D</td> <td>&lt;5000'=NEG</td> <td>&lt;5000'=12'</td> <td>YES</td> <td>74</td> <td>&lt;5000'=NO</td> <td>N/A</td> <td>1500</td> <td>64</td> </tr> </tbody> </table>												GROUND SNOW LOAD	WIND DESIGN		SEISMIC DESIGN CAT	SUBJECT TO DAMAGE FROM			Winter Design Temp	ICE BARRIER UNDERCAYMENT REQUIRED	FLOOD HAZARDS	AIR FREEZING INDEX	MEAN ANNUAL TEMP	Speed (mph)	Topographic effects	Weathering	Frost Line Depth	Termitic	0	110	NO	D	<5000'=NEG	<5000'=12'	YES	74	<5000'=NO	N/A	1500	64	<p><b>G. GENERAL MATERIAL SPECIFICATIONS</b></p> <p>1. LUMBERT. ALL JOISTS, RAFTERS, BEAMS, AND POSTS SHALL BE NO. 2 GRADE DOUGLAS FIR-LARCH OR BETTER. STUDS NOT MORE THAN 8 FEET LONG SHALL BE STUD-GRADE DOUGLAS FIR-LARCH OR BETTER WHEN SUPPORTING NOT MORE THAN ONE FLOOR, ROOF, AND CEILING. STUDS LONGER THAN 8 FEET SHALL BE NO. 2 GRADE DOUGLAS FIR-LARCH OR BETTER.</p> <p>2. STRUCTURAL PLYWOOD SHALL CONFORM TO COMMERCIAL STANDARD DOC PS 1-09 AND HAVE A PANEL GRADE OF C-D. WOOD BASED STRUCTURAL-USE PANELS (I.E. ORIENTED STRAND BOARD) SHALL CONFORM TO THE APA PRP-108 PERFORMANCE STANDARD OF THE VOLUNTARY PRODUCT STANDARD DOC PS 2-10. "PERFORMANCE STANDARD FOR WOOD-BASED STRUCTURAL-USE PANELS". PUBLISHED BY THE DEPARTMENT OF COMMERCE AND THE AMERICAN PLYWOOD ASSOCIATION. ALL PLYWOOD AND STRUCTURAL-USE PANELS SHALL BE APA RATED SHEATHING, EXPOSURE 1, SHEATHING EXPOSED TO WEATHER SHALL BE GRADE C-C EXTERIOR WITH A RANGE INDEX AS TO MATCH BODY OF DIAGRAM SPECIFIED.</p> <p>3. CONCRETE. THE QUALITY AND DESIGN OF CONCRETE SHALL BE IN ACCORDANCE WITH 2022 CALIFORNIA BUILDING CODE (CBC), EXCEPT ITEMS NOT SPECIFICALLY COVERED THEREIN SHALL ALSO CONFORM TO ACI 318-14.</p> <p>4. REINFORCING STEEL. REINFORCING STEEL USED IN CONSTRUCTION OF REINFORCED CONCRETE STRUCTURES SHALL BE DEFORMED AND COMPLY WITH ASTM A 615., GRADE 40. (CRC R403.1.3.5.1)</p> <p>5. FASTENERS FOR PRESERVATIVE-TREATED WOOD. FASTENERS FOR PRESERVATIVE-TREATED AND FIRE-RETARDANT-TREATED WOOD -- INCLUDING NUTS AND WASHERS -- SHALL BE OF HOT DIPPED ZINC-COATED GALVANIZED STEEL, STAINLESS STEEL, SILICON BRONZE, OR COPPER. (CRC R317.3)</p> <p>EXCEPTION: 1/2-INCH DIAMETER OR GREATER STEEL BOLTS</p> <p>EXCEPTION: FASTENERS OTHER THAN NAILS AND TIMBER RIVETS MAY BE OF MECHANICALLY DEPOSITED ZINC-COATED STEEL WITH COATING WEIGHTS IN ACCORDANCE WITH ASTM B 695, CLASS 55 MINIMUM</p> <p>EXCEPTION: PLAIN CARBON STEEL FASTENERS ACCEPTABLE IN SBX/DOT AND ZINC BORATE PRESERVATIVE-TREATED WOOD IN AN INTERIOR, DRY ENVIRONMENT</p> <p>6. FASTENERS FOR FIRE-RETARDANT-TREATED WOOD. FASTENERS FOR FIRE-RETARDANT-TREATED WOOD USED IN EXTERIOR APPLICATIONS OR WET OR DAMP LOCATIONS SHALL BE OF HOT DIPPED ZINC-COATED GALVANIZED STEEL, STAINLESS STEEL, SILICON BRONZE, OR COPPER. (CRC R317.3.3)</p> <p>7. WALL FLASHING. APPROVED CORROSION-RESISTANT FLASHING SHALL BE APPLIED SHINGLE FASHION AT THE FOLLOWING LOCATIONS TO PREVENT ENTRY OF WATER INTO THE WALL CAVITY OR PENETRATION OF WATER TO THE BUILDING STRUCTURAL FRAMING COMPONENTS (CRC R703.8):</p> <p>7.8. EXTERIOR DOOR AND WINDOW OPENINGS, EXTENDING TO THE SURFACE OF THE EXTERIOR WALL FINISH OR TO THE WATER-RESISTIVE BARRIER FOR SUBSEQUENT DRAINAGE</p> <p>7.9. AT THE INTERSECTION OF CHIMNEYS OR OTHER MASONRY CONSTRUCTION WITH FRAME OR STUCCO WALLS, WITH PROJECTIONS LIPS ON BOTH SIDES UNDER STUCCO COPINGS</p> <p>7.10. UNDER AND AT THE ENDS OF MASONRY, WOOD, OR METAL COPINGS AND SILLS</p> <p>7.11. CONTINUOUSLY ABOVE ALL PROJECTIONS WOOD TRIM</p> <p>7.12. WHERE EXTERIOR PORCHES, DECKS, OR STAIRS ATTACH TO A WALL OR FLOOR</p> <p>7.13. AT WALL AND ROOF INTERSECTIONS</p> <p>7.14. AT BUILT-IN GUTTERS</p> <p><b>H. LIGHTING</b></p> <p>RESIDENTIAL LIGHTING. CA ENERGY CODE 150.0(K)</p> <p>1. LUMINAIRE REQUIREMENTS.</p> <p>1.1. LUMINAIRE EFFICACY. ALL INSTALLED LUMINAIRES SHALL MEET THE REQUIREMENTS IN TABLE 150.0-A.</p> <p>EXCEPTION 1 TO SECTION 150.0(K)1A: INTEGRATED DEVICE LIGHTING. <b>ROD CARSEY CONSULTING &amp; PLAN CHECK</b></p> <p>EXCEPTION 2 TO SECTION 150.0(K)1A: NAVIGATION LIGHTING SUCH AS NIGHT LIGHTS, STEP LIGHTS, AND PATH LIGHTS LESS THAN 5 WATTS.</p> <p>EXCEPTION 3 TO SECTION 150.0(K)1A: CABINET LIGHTING. LIGHTING INTERNAL TO DRAWERS, CABINETRY AND LINEN CLOSETS WITH AN EFFICACY OF 45 LUMENS PER WATT OR GREATER.</p> <p>1.2. SCREW-BASED LUMINAIRES. SCREW-BASED LUMINAIRES SHALL CONTAIN LAMPS THAT COMPLY WITH REFERENCE JOINT APPENDIX JAB.</p> <p>1.3. RECESSED DOWNLIGHT LUMINAIRES IN CEILINGS. LUMINAIRES RECESSED INTO CEILINGS SHALL MEET ALL OF THE FOLLOWING REQUIREMENTS:</p> <p>i. SHALL NOT CONTAIN SCREW BASE LAMP SOCKETS; AND</p> <p>ii. HAVE A LABEL THAT CERTIFIES THE LUMINAIRE IS AIRTIGHT WITH AIR LEAKAGE LESS THAN 2.0 CFM AT 75 PASCALS WHEN TESTED IN ACCORDANCE WITH ASTM E283. AN EXHAUST FAN HOUSING WITH INTEGRAL LIGHT SHALL NOT BE REQUIRED TO BE CERTIFIED AIRTIGHT; AND</p> <p>iii. BE SEALED WITH A GASKET OR CAULK BETWEEN THE LUMINAIRE HOUSING AND CEILING, AND HAVE ALL AIR LEAK PATHS BETWEEN CONDITIONED AND UNCONDITIONED SPACES SEALED WITH A GASKET OR CAULK, OR BE INSTALLED PER MANUFACTURER'S INSTRUCTIONS TO MAINTAIN AIRTIGHTNESS BETWEEN THE LUMINAIRE HOUSING AND CEILING; AND</p> <p>iv. MEET THE CLEARANCE AND INSTALLATION REQUIREMENTS OF CALIFORNIA ELECTRICAL CODE SECTION 410.116 FOR RECESSED LUMINAIRES.</p> <p>EXCEPTION TO SECTIONS 150.0(K)1CII AND III: RECESSED LUMINAIRES MARKED FOR USE IN FIRE-RATED INSTALLATIONS EXTRUDED INTO CEILING SPACE AND RECESSED LUMINAIRES INSTALLED IN NONINSULATED CEILINGS.</p> <p>1.4. LIGHT SOURCES IN ENCLOSED OR RECESSED LUMINAIRES. LAMPS AND OTHER SEPARABLE LIGHT SOURCES THAT ARE NOT COMPLIANT WITH THE JAB ELEVATED TEMPERATURE REQUIREMENTS, INCLUDING MARKING REQUIREMENTS, SHALL NOT BE INSTALLED IN ENCLOSED OR RECESSED LUMINAIRES.</p> <p>1.5. BLANK ELECTRICAL BOXES. THE NUMBER OF ELECTRICAL BOXES THAT ARE MORE THAN 5 FEET ABOVE THE FINISHED FLOOR AND DO NOT CONTAIN A LUMINAIRE OR OTHER DEVICE SHALL BE NO GREATER THAN THE NUMBER OF BEDROOMS. THESE ELECTRICAL BOXES MUST BE SERVED BY A DIMMER, VACANCY SENSOR CONTROL, LOW VOLTAGE WIRING OR FAN SPEED CONTROL.</p> <p>2. INDOOR LIGHTING CONTROLS.</p> <p>2.1. LIGHTING SHALL HAVE READILY ACCESSIBLE WALL-MOUNTED CONTROLS THAT ALLOW THE LIGHTING TO BE MANUALLY TURNED ON AND OFF.</p> <p>EXCEPTION TO SECTION 150.0(K)2A: CEILING FANS MAY PROVIDE CONTROL OF INTEGRATED LIGHTING VIA A REMOTE CONTROL.</p> <p>2.2. NO CONTROLS SHALL BYPASS A DIMMER, OCCUPANT SENSOR OR VACANCY SENSOR FUNCTION WHERE THAT DIMMER OR SENSOR HAS BEEN INSTALLED TO COMPLY WITH SECTION 150.0(K).</p> <p>2.3. LIGHTING CONTROLS SHALL COMPLY WITH THE APPLICABLE REQUIREMENTS OF SECTION 110.9.</p> <p>2.4. AN ENERGY MANAGEMENT CONTROL SYSTEM (EMCS) OR A MULTISCENE PROGRAMMABLE CONTROL MAY BE USED TO COMPLY WITH DIMMING, OCCUPANCY AND LIGHTING CONTROL REQUIREMENTS IN SECTION 150.0(K)2 IF IT PROVIDES THE FUNCTIONALITY OF THE SPECIFIED CONTROLS IN ACCORDANCE WITH SECTION 110.9, AND THE PHYSICAL CONTROLS SPECIFIED IN SECTION 150.0(K)2A.</p> <p><b>I. ROOFING AND WEATHERPROOFING</b></p> <p>1. ROOF COVERING. ALL ROOF COVERING SHALL BE INSTALLED PER APPLICABLE REQUIREMENTS OF CBC 1507. ROOF COVERINGS SHALL BE AT LEAST CLASS A RATED IN ACCORDANCE WITH ASTM E 108 OR UL 790, WHICH SHALL INCLUDE COVERINGS OF SLATE, CLAY OR CONCRETE ROOF TILE, EXPOSED CONCRETE ROOF DECK, FERROUS OR COPPER SHINGLES OR SHEETS.</p> <p>2. ROOF FLASHING. FLASHING SHALL BE INSTALLED AT WALL AND ROOF INTERSECTIONS, AT GUTTERS, WHEREVER THERE IS A CHANGE IN ROOF SLOPE OR DIRECTION, AND AROUND ROOF OPENINGS. WHERE FLASHING IS OF METAL, THE METAL SHALL BE CORROSION-RESISTANT WITH A THICKNESS OF NOT LESS THAN 0.019 INCH (NO. 26 GALVANIZED SHEET). (CRC R903.2.1)</p> <p>3. CRICKETS AND SADDLES. A CRICKET OR SADDLE SHALL BE INSTALLED ON THE RIDGE SIDE OF ANY CHIMNEY OR PENETRATION MORE THAN 30 INCHES WIDE AS MEASURED PERPENDICULAR TO THE SLOPE. CRICKET OR SADDLE COVERING SHALL BE SHEET METAL OR THE SAME MATERIAL AS THE ROOF COVERING. (CRC R903.2.2)</p> <p>4. WATER-RESISTIVE BARRIER. A MINIMUM OF ONE LAYER OF NO. 15 ASPHALT FELT SHALL BE ATTACHED TO STUDS OR SHEATHING OF ALL EXTERIOR WALLS. SUCH FELT OR MATERIAL SHALL BE APPLIED HORIZONTALLY, WITH THE UPPER LAYER LAPPED OVER THE LOWER LAYER MINIMUM 2 INCHES. WHERE JOINTS OCCUR, FELT SHALL BE LAPPED MINIMUM 6 INCHES. THE FELT SHALL BE CONTINUOUS TO THE TOP OF WALLS AND TERMINATED AT PENETRATIONS AND BUILDING APPENDAGES IN A MANNER TO MAINTAIN A WEATHER-RESISTANT EXTERIOR WALL ENVELOPE. (CRC R703.2)</p> <p>5. DAMPPROOFING. DAMPPROOFING MATERIALS FOR FOUNDATION WALLS ENCLOSING USABLE SPACE BELOW GRADE SHALL BE INSTALLED ON THE EXTERIOR SURFACE OF THE WALL, AND SHALL EXTEND FROM THE TOP OF THE FOOTING TO FINISHED GRADE. (CRC R406.1)</p> <p>6. WEEP SCREED. A MINIMUM 0.019-INCH (NO. 26 GALVANIZED SHEET GAGE), CORROSION-RESISTANT WEEP SCREED PLASTIC WEEP SCREED WITH A MINIMUM VERTICAL ATTACHMENT FLANGE OF 3-1/2 INCHES SHALL BE PROVIDED BELOW THE FOUNDATION PLATE LINE ON EXTERIOR STUD WALLS IN ACCORDANCE WITH ASTM C 92. THE WEEP SCREED SHALL BE PLACED A MINIMUM 4 INCHES ABOVE THE EARTH OR 2 INCHES ABOVE PAVED AREAS AND SHALL BE OF A TYPE ALLOWING TRAPPED WATER TO DRAIN TO THE EXTERIOR OF THE BUILDING. (CRC R703.7.2.1)</p>											
GROUND SNOW LOAD	WIND DESIGN		SEISMIC DESIGN CAT	SUBJECT TO DAMAGE FROM			Winter Design Temp	ICE BARRIER UNDERCAYMENT REQUIRED	FLOOD HAZARDS	AIR FREEZING INDEX	MEAN ANNUAL TEMP																																									
	Speed (mph)	Topographic effects		Weathering	Frost Line Depth	Termitic																																														
0	110	NO	D	<5000'=NEG	<5000'=12'	YES	74	<5000'=NO	N/A	1500	64																																									
<p><b>REVISIONS</b></p> <p>— — — — —</p>																																																				
PROJECT TITLE	CITY OF HANFORD - PRE-REVIEWED ADU PROGRAM			COVER		DATE 10/28/2024																																														
ADU SQFT	SHEET DESCRIPTION			AGENCY	SJN REAP																																															
<p><b>375</b></p>																																																				
<p><b>DRAWING SCALE</b> <b>BUILDING DIVISION</b> <b>APPROVED</b></p>																																																				
<p><b>CITY OF HANFORD</b> THIS SET OF PLANS AND SPECIFICATIONS MUST BE KEPT ON THE JOB AT ALL TIMES AND NO CHANGES OR ALTERATIONS SHALL BE MADE EXCEPT BY THE BUILDING DIVISION.</p>																																																				
<p><b>THE STAMPING OF THIS PLAN AND SPECIFICATIONS SHALL NOT BE HELD TO PERMIT OR TO BE AN APPROVAL OF THE VIOLATION OF ANY PROVISIONS OF ANY CITY ORDINANCE OR STATE LAW. "REVIEWED FOR CODE COMPLIANCE."</b></p>																																																				

DISCLAIMER:  
BY USING THESE STANDARD PLANS, THE USER AGREES TO RELEASE THE CITY OF HANFORD FROM ANY AND ALL CLAIMS, LIABILITIES, SUITS AND DEMANDS ON ACCOUNT OF ANY INJURY, DAMAGE, OR DEATH, OR ECONOMIC LOSSES, ARISING OUT OF THE USE OF THESE PLANS, DOES NOT ELIMINATE OR REDUCE THE USER'S RESPONSIBILITY TO VERIFY ANY AND ALL INFORMATION.



PROJECT TITLE	CITY OF HANFORD - PRE-REVIEWED ADU PROGRAM	COVER	DATE
ADU SQFT	SHEET DESCRIPTION	AGENCY	SJN REAP

**375**

**DRAWING SCALE** **BUILDING DIVISION** **APPROVED**

**CITY OF HANFORD**  
THIS SET OF PLANS AND SPECIFICATIONS  
MUST BE KEPT ON THE JOB AT ALL TIMES AND  
NO CHANGES OR ALTERATIONS SHALL BE  
MADE EXCEPT BY THE BUILDING DIVISION.

**THE STAMPING OF THIS PLAN AND  
SPECIFICATIONS SHALL NOT BE HELD TO  
PERMIT OR TO BE AN APPROVAL OF THE  
VIOLATION OF ANY PROVISIONS OF ANY CITY  
ORDINANCE OR STATE LAW. "REVIEWED FOR  
CODE COMPLIANCE."**

*Mitchell Cook*

12/11/2025

#### J. DRAINAGE NOTES

1. SURFACE DRAINAGE SHALL BE DIVERTED TO A STORM SEWER CONVEYANCE OR OTHER APPROVED POINT OF COLLECTION THAT DOES NOT CREATE A HAZARD [CRC R401.3].
2. LOTS SHALL BE GRADED TO DRAIN SURFACE WATER AWAY FROM FOUNDATION WALLS A MINIMUM OF 6 INCHES FOR A DISTANCE OF 10 FEET. EXCEPTION: WHERE SLOPES OR OTHER PHYSICAL BARRIERS PROHIBIT 6 INCHES OF FALL FOR 10 FEET, DRAINS OR SWALES SHALL BE CONSTRUCTED TO ENSURE DRAINAGE AWAY FROM THE STRUCTURE. WHEN DRAINS OR SWALES ARE USED FOR THIS PURPOSE:
  - 2.1. PROVIDE A MINIMUM 5% SLOPE FROM FOUNDATION TO DRAIN/SWALE,
  - 2.2. DRAIN/SWALE SHOULD BE LOCATED AS FAR AS IS PRACTICAL FROM THE FOUNDATION TO MAXIMIZE FALL AND
  - 2.3. DRAIN/SWALE IS TO SLOPE A MINIMUM OF 2%.
3. IMPERVIOUS SURFACES WITHIN 10 FEET OF THE BUILDING FOUNDATION SHALL BE SLOPED NOT LESS THAN 2 PERCENT AWAY FROM THE BUILDING.
4. ON GRADED SITES, THE TOP OF ANY EXTERIOR FOUNDATION (FINISH FLOOR ELEVATION) SHALL EXTEND ABOVE THE ELEVATION OF THE STREET GUTTER AT POINT OF DISCHARGE OR THE INLET OF AN APPROVED DRAINAGE DEVICE NOT LESS THAN 12 INCHES PLUS 2 PERCENT [CRC R403.1.7.3].
5. ALTERNATE SETBACKS AND CLEARANCES ARE PERMITTED, SUBJECT TO THE APPROVAL OF THE BUILDING OFFICIAL [CRC R403.1.7.4].

#### K. STREET ADDRESSING

1. SEPARATE STREET ADDRESSING IS REQUIRED FOR THE ADU. INSTALL STREET ADDRESS NUMERALS, AT LEAST FOUR INCHES HIGH WITH MINIMUM  $\frac{1}{2}$ -INCH STROKE, MOUNTED ON A CONTRASTING BACKGROUND ON FRONT OF THE BUILDING [CRC R319.1].

#### HERS SPECIAL FEATURES

##### REQUIRED SPECIAL FEATURES

The following are features that must be installed as condition for meeting the modeled energy performance for this computer analysis.

- Ceiling has high level of insulation
- Insulation below roof deck
- Window overhangs and/or fins

##### HERS FEATURE SUMMARY

The following is a summary of the features that must be field-verified by a certified HERS Rater as a condition for meeting the modeled energy performance for this computer analysis. Additional detail is provided in the building tables below. Registered CF2Rs and CF3Rs are required to be completed in the HERS Registry

- Quality insulation installation (QII)
- Indoor air quality ventilation
- Kitchen range hood
- Verified heat pump rated heating capacity

TABLE R602.3(1)  
FASTENER SCHEDULE FOR STRUCTURAL MEMBERS

ITEM	DESCRIPTION OF BUILDING ELEMENTS	NUMBER AND TYPE OF FASTENER <sup>b,c</sup>	SPACING OF FASTENERS
Roof			
1	Blocking between joists or rafters to top plate, toe nail	3-8d (2 $\frac{1}{2}$ " x 0.113")	—
2	Ceiling joists to plate, toe nail	3-8d (2 $\frac{1}{2}$ " x 0.113")	—
3	Ceiling joists not attached to parallel rafter, laps over partitions, face nail	3-10d	—
4	Collar tie to rafter, face nail or 1 $\frac{1}{4}$ " x 20 gage ridge strap	3-10d (3" x 0.128")	—
5	Rafter or roof truss to plate, toe nail	3-16d box nails (3 $\frac{1}{2}$ " x 0.135") or 3-10d common nails (3" x 0.148")	2 toe nails on one side and 1 toe nail on opposite side of each rafter or truss <sup>d</sup>
6	Roof rafters to ridge, valley or hip rafters: toe nail face nail	4-16d (3 $\frac{1}{2}$ " x 0.135") 3-16d (3 $\frac{1}{2}$ " x 0.135")	—
Wall			
7	Built-up studs-face nail	10d (3" x 0.128")	24" o.c.
8	Abutting studs at intersecting wall corners, face nail	16d (3 $\frac{1}{2}$ " x 0.135")	12" o.c.
9	Built-up header, two pieces with 1 $\frac{1}{2}$ " spacer	16d (3 $\frac{1}{2}$ " x 0.135")	16" o.c. along each edge
10	Continued header, two pieces	16d (3 $\frac{1}{2}$ " x 0.135")	16" o.c. along each edge
11	Continuous header to stud, toe nail	4-8d (2 $\frac{1}{2}$ " x 0.113")	—
12	Double studs, face nail	10d (3" x 0.128")	24" o.c.
13	Double top plates, face nail	10d (3" x 0.128")	—
14	Double top plates, minimum 24-inch offset of end joints, face nail in lapped area	8-16d (3 $\frac{1}{2}$ " x 0.135")	—
15	Sole plate to joist or blocking, face nail	16d (3 $\frac{1}{2}$ " x 0.135")	16" o.c.
16	Sole plate to joist or blocking at braced wall panels	3-16d (3 $\frac{1}{2}$ " x 0.135")	16" o.c.
17	Stud to sole plate, toe nail	3-8d (2 $\frac{1}{2}$ " x 0.113") or 2-16d (3 $\frac{1}{2}$ " x 0.135")	—
18	Top or sole plate to stud, end nail	2-16d (3 $\frac{1}{2}$ " x 0.135")	—
19	Top plates, laps at corners and intersections, face nail	2-10d (3" x 0.128")	—
20	1" brace to each stud and plate, face nail	2-8d (2 $\frac{1}{2}$ " x 0.113") 2 staples 1 $\frac{1}{4}$ "	—
21	1" x 6" sheathing to each bearing, face nail	2-8d (2 $\frac{1}{2}$ " x 0.113") 2 staples 1 $\frac{1}{4}$ "	—
22	1" x 8" sheathing to each bearing, face nail	2-8d (2 $\frac{1}{2}$ " x 0.113") 3 staples 1 $\frac{1}{4}$ "	—
23	Wider than 1" x 8" sheathing to each bearing, face nail.	3-8d (2 $\frac{1}{2}$ " x 0.113") 4 staples 1 $\frac{1}{4}$ "	—
Floor			
24	Joist to sill or girder, toe nail	3-8d (2 $\frac{1}{2}$ " x 0.113")	—
25	Rim joist to top plate, toe nail (roof applications also)	8d (2 $\frac{1}{2}$ " x 0.113")	6" o.c.
26	Rim joist or blocking to sill plate, toe nail	8d (2 $\frac{1}{2}$ " x 0.113")	6" o.c.
27	1" x 6" subfloor or less to each joist, face nail	2-8d (2 $\frac{1}{2}$ " x 0.113") 2 staples 1 $\frac{1}{4}$ "	—
28	2" subfloor to joist or girder, blind and face nail	2-16d (3 $\frac{1}{2}$ " x 0.135")	—
29	2" planks (plank & beam - floor & roof)	2-16d (3 $\frac{1}{2}$ " x 0.135")	at each bearing
30	Built-up girders and beams, 2-inch lumber layers	10d (3" x 0.128")	Nail each layer as follows: 32" o.c. at top and bottom and staggered. Two nails at ends and at each splice.
31	Ledger strip supporting joists or rafters	3-16d (3 $\frac{1}{2}$ " x 0.135")	At each joist or rafter
Wood structural panels, subfloor, roof and interior wall sheathing to framing and particleboard wall sheathing to framing			
32	3 $\frac{1}{2}$ " - 1 $\frac{1}{2}$ "	6d common (2" x 0.113") nail (subfloor, wall) 8d common (2 $\frac{1}{2}$ " x 0.131") nail (roof) <sup>e</sup>	6 12 <sup>f</sup>
33	1 $\frac{1}{2}$ " - 1"	8d common nail (2 $\frac{1}{2}$ " x 0.131")	6 12 <sup>f</sup>
34	1 $\frac{1}{2}$ " - 1 $\frac{1}{4}$ "	10d common (3" x 0.148") nail or 8d (2 $\frac{1}{2}$ " x 0.131") deformed nail	6 12
Other wall sheathing <sup>g</sup>			
35	1 $\frac{1}{2}$ " structural cellulose fiberboard sheathing	1 $\frac{1}{4}$ " galvanized roofing nail, 1 $\frac{1}{16}$ " crown or 1" crown staple 16 ga., 1 $\frac{1}{4}$ " long	3 6
36	2 $\frac{1}{2}$ " structural cellulose fiberboard sheathing	1 $\frac{1}{4}$ " galvanized roofing nail, 1 $\frac{1}{16}$ " crown or 1" crown staple 16 ga., 1 $\frac{1}{4}$ " long	3 6
37	1 $\frac{1}{2}$ " gypsum sheathing <sup>h</sup>	1 $\frac{1}{4}$ " galvanized roofing nail; staple galvanized, 1 $\frac{1}{2}$ " long; 1 $\frac{1}{4}$ " screws, Type W or S	7 7
38	5 $\frac{1}{8}$ " gypsum sheathing <sup>h</sup>	1 $\frac{1}{4}$ " galvanized roofing nail; staple galvanized, 1 $\frac{1}{4}$ " long; 1 $\frac{1}{4}$ " screws, Type W or S	7 7
Wood structural panels, combination subfloor underlayment to framing			
39	3 $\frac{1}{4}$ " and less	6d deformed (2" x 0.120") nail or 8d common (2 $\frac{1}{2}$ " x 0.131") nail	6 12
40	7 $\frac{1}{8}$ " - 1"	8d common (2 $\frac{1}{2}$ " x 0.131") nail or 8d deformed (2 $\frac{1}{2}$ " x 0.120") nail	6 12
41	1 $\frac{1}{2}$ " - 1 $\frac{1}{4}$ "	10d common (3" x 0.148") nail or 8d deformed (2 $\frac{1}{2}$ " x 0.120") nail	6 12

These plans and documents have been reviewed for compliance with the applicable codes requirements of the jurisdiction. The stamping of these plans shall not be held to permit or be an approval of any violation of applicable codes and standards nor relieve the owner, design professional of record or contractor of compliance with applicable codes and standards

ROD CARSEY CONSULTING & PLAN CHECK SERVICE

- Nails are smooth-common, box or deformed shanks except where otherwise stated. Nails used for framing and sheathing connections shall have minimum average bending yield strengths as shown: 80 ksi for shank diameter of 0.192 inch (20d common nail), 90 ksi for shank diameters larger than 0.142 inch but not larger than 0.177 inch, and 100 ksi for shank diameters of 0.142 inch or less.
- Staples are 16 gage wire and have a minimum 7/16-inch on diameter crown width.
- Nails shall be spaced at not more than 6 inches on center at all supports where spans are 48 inches or greater.
- Four-foot by 8-foot or 4-foot by 9-foot panels shall be applied vertically.
- Spacing of fasteners not included in this table shall be based on Table R602.3(2).
- For wood structural panel roof sheathing attached to cable end roof framing and to intermediate supports within 48 inches of roof edges and ridges, nails shall be spaced at 6 inches on center where the ultimate design wind speed is less than 130 mph and shall be spaced 4 inches on center where the ultimate design wind speed is 130 mph or greater but less than 140 mph.
- Gypsum sheathing shall conform to ASTM C1396 and shall be installed in accordance with GA 253. Fiberboard sheathing shall conform to ASTM C208.
- Spacing of fasteners on floor sheathing panel edges applies to panel edges supported by framing members and required blocking and at floor perimeters only. Spacing of fasteners on roof sheathing panel edges applies to panel edges supported by framing members and required blocking. Blocking of roof or floor sheathing panel edges perpendicular to the framing members need not be provided except as required by other provisions of this code. Floor perimeter shall be supported by framing members or solid blocking.
- Where a rafter is fastened to an adjacent parallel ceiling joist in accordance with this schedule, provide two toe nails on one side of the rafter and toe nails from the ceiling joist to top plate in accordance with this schedule. The toe nail on the opposite side of the rafter shall not be required.
- RSRS-01 is a Roof Sheathing Ring Shank nail meeting the specifications in ASTM F1667.

DISCLAIMER:  
BY USING THESE STANDARD PLANS, THE USER AGREES TO RELEASE THE CITY OF HANFORD FROM ANY AND ALL CLAIMS, LIABILITIES, SUITS AND DEMANDS ON ACCOUNT OF ANY INJURY, DAMAGE, OR LOSS TO PERSONS OR PROPERTY, ARISING OUT OF THE USE OF THESE CONSTRUCTION DOCUMENTS. THE USE OF THESE PLANS DOES NOT ELIMINATE OR REDUCE THE USER'S RESPONSIBILITY TO VERIFY ANY AND ALL INFORMATION.



PROJECT TITLE	CITY OF HANFORD - PRE-REVIEWED ADU PROGRAM	
SHEET DESCRIPTION	COVER	
AGENCY	SJV REAP	DATE 10/28/2024
ADU SQFT	375	


DRAWING SCALE	BUILDING DIVISION
APPROVED	

THIS SET OF PLANS AND SPECIFICATIONS SHALL BE KEPT ON THE JOB AT ALL TIMES AND NO CHANGES OR ALTERATIONS SHALL BE MADE EXCEPT BY THE BUILDING DIVISION.

THE STAMPING OF THIS PLAN AND SPECIFICATIONS SHALL NOT BE HELD TO PERMIT OR TO BE AN APPROVAL OF THE VIOLATION OF ANY PROVISIONS OF ANY CITY ORDINANCE OR STATE LAW. "REVIEWED FOR CODE COMPLIANCE."

By: *Mitchell Cook*

12/11/2025



DASHED LINE: UPPER CABINETS SHALL BE A  
MINIMUM OF 18" ABOVE FINISHED DECK OR THE  
OOD IS TO BE INSTALLED PER MANUFACTURER'S  
REQUIREMENTS WITH CLEARANCES AS REQUIRED  
BY THE RANG/ COOKTOP MANUFACTURER'S  
INSTALLATION INSTRUCTIONS.



for compliance  
requirements of  
of these plans  
an approval of a  
and standards  
professional of  
compliance with

## LEGEND

WINDOW SCHEDULE				
MARK	DIMENSION	TYPE	TEMPERED	NOTES
(A)	4'-0" x 4'-0"	SLIDING	—	—
(B)	3'-0" x 3'-0"	SLIDING	—	—
(C)	3'-0" x 1'-0"	SLIDING	TEMPERED GLAZING	6' ABOVE FLOOR

MINIMUM LI = 0.32 SHGC = 0.28

THE BOTTOM OF THE CLEAR OPENING OF WINDOWS IN SLEEPING ROOMS SHALL NOT BE MORE THAN 44" ABOVE THE FLOOR (CRC R310.2.3)

ALL WINDOWS TO BE INSTALLED WITH OVERHANGS OR FINS TO MEET HER'S ENERGY ANALYSIS REQUIREMENTS

DOOR SCHEDULE			
MARK	DIMENSION	TYPE	NOTES
①	3'-0" x 6'-8"	SWINGING	1-3/8" SOLID CORE
②	2'-6" x 6'-8"	BI-FOLD	LAUNDRY COVERING w/VENTILATION SLATS
③	5'-0" x 6'-8"	SLIDING	5'-6" CLOSET
④	2'-6" x 6'-8"	SWINGING	1-3/8" HOLLOW CORE
⑤	3'-0" x 6'-8"	SWINGING	1-3/8" HOLLOW CORE

EXCERPT FROM R602.3.3 – BEARING STUDS  
WHERE JOISTS, TRUSSES OR RAFTERS ARE SPACED MORE THAN 16 INCHES (406 MM) ON CENTER AND THE BEARING STUDS BELOW ARE SPACED 24 INCHES (610 MM) ON CENTER, SUCH MEMBERS SHALL BEAR WITHIN 5 INCHES (127 MM) OF THE STUDS BENEATH.

## *AGING-IN-PLACE*

---

AGING-IN-PLACE DESIGN AND FALL PREVENTION. NEWLY CONSTRUCTED DWELLINGS SUBJECT TO THE REQUIREMENTS OF THIS CODE SHALL BE DESIGNED AND CONSTRUCTED IN ACCORDANCE WITH SECTIONS R327.1.1 THROUGH R327.1.4.PAGE

AT LEAST ONE BATHROOM ON THE ENTRY LEVEL SHALL BE PROVIDED WITH REINFORCEMENT INSTALLED IN ACCORDANCE WITH THIS SECTION. WHERE THERE IS NO BATHROOM ON THE ENTRY LEVEL, AT LEAST ONE BATHROOM ON THE SECOND OR THIRD FLOOR OF THE DWELLING SHALL COMPLY WITH THIS SECTION. [CRC R327.1.1]

INFORMATION AND/OR DRAWINGS IDENTIFYING THE LOCATION OF GRAB BAR REINFORCEMENT SHALL BE PLACED IN THE OPERATION AND MAINTENANCE MANUAL IN ACCORDANCE WITH THE CALIFORNIA GREEN BUILDING STANDARDS CODE, CHAPTER 4, DIVISION 4.4.[CRC R327.1.1.1]

ELECTRICAL RECEPTACLE OUTLET, SWITCH AND CONTROL HEIGHTS. ELECTRICAL RECEPTACLE OUTLETS, SWITCHES AND CONTROLS (INCLUDING CONTROLS FOR HEATING, VENTILATION AND AIR CONDITIONING) INTENDED TO BE USED BY OCCUPANTS SHALL BE LOCATED NO MORE THAN 48 INCHES MEASURED FROM THE TOP OF THE OUTLET BOX AND NOT LESS THAN 15 INCHES MEASURED FROM THE BOTTOM OF THE OUTLET BOX ABOVE THE FINISH FLOOR. [CRC R327.1.2]

EFFECTIVE JULY 1, 2024, AT LEAST ONE BATHROOM AND ONE BEDROOM ON THE ENTRY LEVEL SHALL PROVIDE A DOORWAY WITH A NET CLEAR OPENING OF NOT LESS THAN 32 INCHES, MEASURED WITH THE DOOR POSITIONED AT AN ANGLE OF 90 DEGREES FROM THE CLOSED POSITION; OR, IN THE CASE OF A TWO- OR THREE-STORY SINGLE FAMILY DWELLING, ON THE SECOND OR THIRD FLOOR OF THE DWELLING IF A BATHROOM OR BEDROOM IS NOT LOCATED ON THE ENTRY LEVEL. [CRC R327.1.3]

DOORBELL BUTTONS OR CONTROLS, WHEN INSTALLED, SHALL NOT EXCEED 48 INCHES (1219.2 MM) ABOVE EXTERIOR FLOOR OR LANDING, MEASURED FROM THE TOP OF THE DOORBELL BUTTON ASSEMBLY. WHERE DOORBELL BUTTONS INTEGRATED WITH OTHER FEATURES ARE REQUIRED TO BE INSTALLED ABOVE 48 INCHES MEASURED FROM THE EXTERIOR FLOOR OR LANDING, A STANDARD DOORBELL BUTTON OR CONTROL SHALL ALSO BE PROVIDED AT A HEIGHT NOT EXCEEDING 48 INCHES ABOVE EXTERIOR FLOOR OR LANDING, MEASURED FROM THE TOP OF THE DOORBELL BUTTON OR CONTROL. [CRC R327.1.4]

## *OPTIONAL ROLL-IN SHOWER PLAN NOTES*

---

NOTE: OPTIONAL ROLL IN SHOWERS OFFERED FOR CONVENIENCE NOT FOR COMPLIANCE WITH  
ACCESSIBILITY STANDARDS.

1. SHOWER COMPARTMENT SEAT
  - MUST BE FOLDING TYPE, NOT TO EXCEED MORE THAN 6 INCHES FROM MOUNTING WALL WHEN FOLDED
  - LOCATED WITHIN 27 INCHES OF SHOWER CONTROLS
  - MOUNTED MINIMUM 17 INCHES AND MAXIMUM 19 INCHES ABOVE BATHROOM FINISHED FLOOR.
  - SEAT INSTALLED ON SIDE WALL ADJACENT TO CONTROLS AND EXTENDING FROM BACK WALL TO POINT WITHIN 3 INCHES OF SHOWER COMPARTMENT ENTRY
  - STRUCTURAL ADEQUACY OF MOUNTING HARDWARE AND FASTENERS TO ACCOMMODATE 250 POUND POINT LOAD APPLIED AT ANY POINT ON THE GRAB BAR, FASTENER, MOUNTING DEVICE, OR SUPPORTING STRUCTURE
2. SHOWER GRAB BARS
  - MOUNTED MINIMUM 33 INCHES AND MAXIMUM 36 INCHES ABOVE SHOWER FLOOR
  - NOT EXTENDING OVER SHOWER SEAT
  - IF CROSS SECTION IS CIRCULAR, MINIMUM 1-1/4" AND MAXIMUM 2" OUTSIDE DIAMETER
  - IF CROSS SECTION IS NON-CIRCULAR, MINIMUM 4" AND MAXIMUM 4.8" PERIMETER AND MAXIMUM 2-1/4" CROSS SECTION DIMENSION
  - GRAB BARS MOUNTED ADJACENT TO A WALL, 1-1/2" ABSOLUTE SPACE BETWEEN WALL AND GRAB BAR
  - MINIMUM 1-1/2" SPACE BETWEEN GRAB BAR AND PROJECTIONS BELOW AND AT ENDS
  - MINIMUM 12 INCH SPACE BETWEEN GRAB BAR AND PROJECTIONS ABOVE
  - SURFACE MATERIAL OF ANY WALLS OR OBJECTS ADJACENT TO GRAB BARS MUST BE FREE OF SHARP OR ABRASIVE ELEMENTS AND HAVE ROUNDED EDGES.
  - STRUCTURAL ADEQUACY OF MOUNTING HARDWARE AND FASTENERS TO ACCOMMODATE 250 POUND POINT LOAD APPLIED AT ANY POINT ON THE GRAB BAR, FASTENER, MOUNTING DEVICE, OR SUPPORTING STRUCTURE
  - WALL REINFORCEMENT TO BE PROVIDED AT LOCATION OF GRAB BARS (E.G. BLOCKING)
  - REINFORCEMENT SHALL BE A SOLID LUMBER OR OTHER CONSTRUCTION MATERIALS APPROVED BY THE ENFORCING AGENCY
  - REINFORCEMENT SHALL NOT BE LESS THAN 2"x8" NOMINAL LUMBER (1-1/2"x7-1/4" ACTUAL DIMENSION) OR OTHER CONSTRUCTION MATERIAL PROVIDING EQUAL HEIGHT AND LOAD CAPACITY. REINFORCEMENT SHALL BE LOCATED BETWEEN 32 INCHES AND 39-1/4 INCHES ABOVE THE FINISHED FLOOR FLUSH WITH THE WALL FRAMING.
  - SHOWER REINFORCEMENTS SHALL BE CONTINUOUS WHERE WALL FRAMING IS PROVIDED.
3. OPERABLE PARTS OF SHOWER CONTROLS AND FAUCETS:
  - INSTALLED ON BACK WALL OF SHOWER COMPARTMENT ADJACENT TO SEAT WALL
  - LOCATED MINIMUM 19 INCHES AND MAXIMUM 27 INCHES FROM SEAT WALL
  - LOCATED ABOVE GRAB BAR BUT NO HIGHER THAN 48 INCHES ABOVE SHOWER FLOOR
  - CENTERLINE AT MINIMUM 39 INCHES AND MAXIMUM 41 INCHES ABOVE SHOWER FLOOR
  - SINGLE-LEVER DESIGN
  - OPERABLE WITH MAXIMUM 5 POUNDS OF FORCE
  - OPERABLE WITH ONE HAND AND WITHOUT TIGHT GRASPING, PINCHING, OR TWISTING OF WRIST
4. SPRAYER UNIT AND ASSOCIATED OPERABLE PARTS SHALL BE PROVIDED PER THE FOLLOWING:
  - OPERABLE PARTS, INCLUDING HANDLE, TO BE INSTALLED ON BACK WALL OF SHOWER COMPARTMENT MINIMUM 19 INCHES AND MAXIMUM 27 INCHES FROM SEAT WALL
  - OPERABLE PARTS LOCATED ABOVE GRAB BAR BUT NO HIGHER THAN 48 INCHES ABOVE SHOWER FLOOR, MEASURED TO TOP OF MOUNTING BRACKET
  - MINIMUM 59 INCH LONG HOSE
  - CAPABLE FOR USE AS FIXED SHOWER HEAD AND HAND HELD SHOWER
  - ON/OFF CONTROL WITH NON-POSITIVE SHUT OFF
  - ADJUSTABLE -HEIGHT SHOWER HEADS ON VERTICAL BAR SHALL NOT OBSTRUCT USE OF BATH TUB GRAB BARS

CITY OF HANFORD BUILDING DIVISION

**3/4" = 1'**

5. WHERE SOAP DISHES ARE PROVIDED, MAXIMUM 40 INCHES ABOVE SHOWER FLOOR AND WITHIN **APPROVED** REACH LIMITS FROM THE SHOWER SEAT

6. MAXIMUM 2.1% SLOPE IN ALL DIRECTIONS OF ROLL-IN SHOWER FLOORS

7. MAXIMUM  $\frac{1}{2}$ " HIGH THRESHOLDS WITH MAXIMUM 50% BEVELED SLOPE AT ROLL-IN SHOWERS

8. WHERE DRAINS ARE PROVIDED AT ROLL-IN SHOWERS, MAXIMUM  $\frac{1}{4}$ " GRATE OPENINGS

**THIS SET OF PLANS AND SPECIFICATIONS  
MUST BE KEPT ON THE JOB AT ALL TIMES AND  
NO CHANGES OR ALTERATIONS SHALL BE  
MADE EXCEPT BY THE BUILDING DIVISION.**

**THE STAMPING OF THIS PLAN AND  
SPECIFICATIONS SHALL NOT BE HELD TO  
PERMIT OR TO BE AN APPROVAL OF THE  
VIOLATION OF ANY PROVISIONS OF ANY CITY**

# UNIVERSITY OF MANFORD



REVISIONS			
PROJECT TITLE	SHEET DESCRIPTION	FLOOR PLAN	AGENCY
CITY OF HANFORD – PRE-REVIEWED ADU PROGRAM			SJV REAP
			DATE
			10/28/2024

ABC SQL 1


375

3 1/4" = 1'  
NS AND SPECIFICATIONS  
THE JOB AT ALL TIMES AND  
ALTERATIONS SHALL BE  
THE BUILDING DIVISION.  
NG OF THIS PLAN AND  
SHALL NOT BE HELD TO  
E AN APPROVAL OF THE  
PROVISIONS OF ANY CITY  
ATE LAW. "REVIEWED FOR  
COMPLIANCE."


A 1

Mitsubishi

~~Mitchell Coa~~



SECTION A - A



SECTION B - B

SECTION KEYNOTES


- 1 WALL INSULATION: R21
- 2 CEILING INSULATION: R49
- 3 ROOF INSULATION: R15
- 4 INTERIOR FINISH:  $\frac{1}{2}$ " GYPSUM BOARD (UNLESS WALL IS FIRE RESISTANT ASSEMBLE)
- 5 EXTERIOR WALL: 2x6 STUD WALL @ 24" O.C.
- 6 INTERIOR WALL: 2x4 STUD WALL @ 24" O.C.
- 7 RADIANT BARRIER IS REQUIRED
- 8 ROOFING: REFER TO ELEVATIONS
- 9 PRE-ENGINEERED, PRE-FABRICATED ROOF TRUSSES (REQUIRED BY APPLICANT AT TIME OF SUBMITTAL)
- 10 EXTERIOR WALL COVERING AS DENOTED AT EXTERIOR ELEVATION. ALL WALL COVERINGS SHALL BE APPLIED OVER WATER RESISTIVE BARRIER APPLIED TO WOOD SHEATHING PER (CRC 703.7.3.1)

NOTE:

1. DESIGN OF ROOF TRUSSES SHALL ACCOMMODATE PHYSICAL DIMENSIONS AND GRAVITY LOAD OF ATTIC MOUNTED AIR HANDLER, AND PV PANEL WEIGHT.
2. VERIFY INSULATION VALUES WITH ENERGY COMPLIANCE REPORT.
3. FOR 1-HOUR FIRE RATED ASSEMBLY" AND "1-HOUR FIRE RATED GABLE END" DETAIL ON SHEETS S4 WHERE REQUIRED.

DISCLAIMER:  
BY USING THESE STANDARD PLANS, THE USER AGREES TO RELEASE THE CITY OF HANFORD FROM ANY AND ALL CLAIMS, LIABILITIES, SUITS AND DEMANDS ON ACCOUNT OF ANY INJURY, DAMAGE, OR LOSS TO PERSONS OR PROPERTY, ARISING OUT OF THE USE OF THESE CONSTRUCTION DOCUMENTS. THE USE OF THESE PLANS DOES NOT ELIMINATE OR REDUCE THE USER'S RESPONSIBILITY TO VERIFY ANY AND ALL INFORMATION.

CITY OF  
HANFORD



REVISIONS

PROJECT TITLE	CITY OF HANFORD - PRE-REVIEWED ADU PROGRAM	
ADU SQFT	STREET DESCRIPTION	SECTIONS
375	SJV REAP	DATE 10/28/2024

DRAWING SCALE  
CITY OF HANFORD BUILDING DIVISION  
APPROVED = 1'

THIS SET OF PLANS AND SPECIFICATIONS  
MUST BE KEPT ON THE JOB AT ALL TIMES AND  
NO CHANGES OR ALTERATIONS SHALL BE  
MADE EXCEPT BY THE BUILDING DIVISION.


THE STAMPING OF THIS PLAN AND  
SPECIFICATIONS SHALL NOT BE HELD TO  
PERMIT OR TO BE AN APPROVAL OF THE  
VIOLATION OF ANY PROVISIONS OF ANY CITY  
ORDINANCE OR STATE LAW. "REVIEWED FOR  
CODE COMPLIANCE."

These plans and documents have been reviewed for compliance with the applicable codes requirements of the jurisdiction. The stamping of these plans shall not be held to permit or be an approval of any violation of applicable codes and standards nor relieve the owner, design professional of record or contractor of compliance with applicable codes and standards


ROD CARSEY CONSULTING & PLAN CHECK  
SERVICE

BY *Mitchell Cook*


12/11/2025




FRONT ELEVATION



LEFT ELEVATION



REAR ELEVATION




RIGHT ELEVATION

These plans and documents have been reviewed for compliance with the applicable codes requirements of the jurisdiction. The stamping of these plans shall not be held to permit or be an approval of any violation of applicable codes and standards nor relieve the owner, design professional of record or contractor of compliance with applicable codes and standards

ROD CARSEY CONSULTING & PLAN CHECK SERVICE

# CITY OF HANFORD



REVISIONS

PROJECT TITLE	CITY OF HANFORD - PRE-REVIEWED ADU PROGRAM	ELEVATION A
ADU SQFT	STREET DESCRIPTION	AGENCY
375	SJV REAP	DATE 10/28/2024

375

DRAWING SCALE

3/8" = 1'

CITY OF HANFORD BUILDING DIVISION  
APPROVED


THIS SET OF PLANS AND SPECIFICATIONS  
MUST BE KEPT ON THE JOB AT ALL TIMES AND  
NO CHANGES OR ALTERATIONS SHALL BE  
MADE EXCEPT BY THE BUILDING DIVISION.

THE STAMPING OF THIS PLAN AND  
SPECIFICATIONS SHALL NOT BE HELD TO  
PERMIT OR TO BE AN APPROVAL OF THE  
VIOLATION OF ANY PROVISIONS OF ANY CITY  
ORDINANCE OR STATE LAW. "REVIEWED FOR  
CODE COMPLIANCE."


*Mitchell Cook*

12/11/2025


DISCLAIMER:  
BY USING THESE STANDARD PLANS, THE USER AGREES TO  
RELEASE THE CITY OF HANFORD FROM ANY AND ALL CLAIMS,  
LIABILITIES, SUITS AND DEMANDS ON ACCOUNT OF ANY  
INJURY, DAMAGE, OR LOSS TO PERSONS OR PROPERTY,  
INCLUDING INJURY OR DEATH, OR ECONOMIC LOSSES, ARISING  
OUT OF THE USE OF THESE CONSTRUCTION DOCUMENTS. THE  
USE OF THESE PLANS DOES NOT ELIMINATE OR REDUCE THE  
USER'S RESPONSIBILITY TO VERIFY ANY AND ALL INFORMATION.




**FRONT ELEVATION**



**LEFT ELEVATION**



**REAR ELEVATION**



**RIGHT ELEVATION**

# CITY OF HANFORD



REVISIONS

PROJECT TITLE

CITY OF HANFORD -

PRE-REVIEWED ADU PROGRAM

SHEET DESCRIPTION

ELEVATION B

ADU SQFT

375

AGENCY

SJV REAP

DATE

10/28/2024

DRAWING SCALE

CITY OF HANFORD

BUILDING DIVISION

APPROVED = 1'


THIS SET OF PLANS AND SPECIFICATIONS  
MUST BE KEPT ON THE JOB AT ALL TIMES AND  
NO CHANGES OR ALTERATIONS SHALL BE  
MADE EXCEPT BY THE BUILDING DIVISION.

THE STAMPING OF THIS PLAN AND  
SPECIFICATIONS SHALL NOT BE HELD TO  
PERMIT OR TO BE AN APPROVAL OF THE  
VIOLATION OF ANY PROVISIONS OF ANY CITY  
ORDINANCE OR STATE LAW. "REVIEWED FOR  
CODE COMPLIANCE."


*Mitchell Cook*

12/11/2025


DISCLAIMER:  
BY USING THESE STANDARD PLANS, THE USER AGREES TO  
RELEASE THE CITY OF HANFORD FROM ANY AND ALL CLAIMS,  
LIABILITIES, SUITS AND DEMANDS ON ACCOUNT OF ANY  
INJURY, DAMAGE, OR LOSS TO PERSONS OR PROPERTY,  
INCLUDING INJURY OR DEATH, OR ECONOMIC LOSSES, ARISING  
OUT OF THE USE OF THESE CONSTRUCTION DOCUMENTS. THE  
USE OF THESE PLANS DOES NOT ELIMINATE OR REDUCE THE  
USER'S RESPONSIBILITY TO VERIFY ANY AND ALL INFORMATION.




FRONT ELEVATION



LEFT ELEVATION



REAR ELEVATION




RIGHT ELEVATION

These plans and documents have been reviewed for compliance with the applicable codes requirements of the jurisdiction. The stamping of these plans shall not be held to permit or be an approval of any violation of applicable codes and standards nor relieve the owner, design professional of record or contractor of compliance with applicable codes and standards

ROD CARSEY CONSULTING & PLAN CHECK SERVICE

# CITY OF HANFORD



REVISIONS

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----


-----

## ARCHITECTURAL DETAILS

### CRAFTSMAN / BUNGALOW



CRAFTSMAN ARCHITECTURE IS KNOWN FOR ITS EMPHASIS ON SIMPLICITY, FUNCTIONALITY, SOLIDLY MADE WITH NATURAL MATERIALS AND NATURE-INSPIRED COLORS AND MOTIFS.




**LIGHT FIXTURES**

### MODERN / FARMHOUSE



MODERN FARMHOUSE ARCHITECTURE BLENDS THE SIMPLICITY AND CHARM OF TRADITIONAL FARMHOUSES WITH CONTEMPORARY DESIGN ELEMENTS AND COLOR SCHEMES.





**LIGHT FIXTURES**

### SPANISH / MEDITERRANEAN



SPANISH MEDITERRANEAN ARCHITECTURE IS CHARACTERIZED BY ITS WARM AND INVITING AESTHETIC, THERE ARE GENERALLY FREE ADAPTATIONS IN THE MISSION STYLE.



ROD CARSEY CONSULTING & PLAN CHECK SERVICE



DISCLAIMER:  
BY USING THESE STANDARD PLANS, THE USER AGREES TO RELEASE THE CITY OF HANFORD FROM ANY AND ALL CLAIMS, LIABILITIES, SUITS AND DEMANDS ON ACCOUNT OF ANY INJURY, DAMAGE, OR LOSS TO PERSONS OR PROPERTY, INCLUDING INJURY OR DEATH, OR ECONOMIC LOSSES, ARISING OUT OF THE USE OF THESE CONSTRUCTION DOCUMENTS. THE USE OF THESE PLANS DOES NOT ELIMINATE OR REDUCE THE USER'S RESPONSIBILITY TO VERIFY ANY AND ALL INFORMATION.

**CITY OF HANFORD**



PROJECT TITLE	CITY OF HANFORD – PRE-REVIEWED ADU PROGRAM	
SHEET DESCRIPTION	ARCHITECTURAL DETAILS	
ADU SQFT	SJN REAP	DATE 10/28/2024

**375**


DRAWING SCALE	BUILDING DIVISION
<b>APPROVED</b>	<b>REVIEWED FOR CODE COMPLIANCE</b>

THIS SET OF PLANS AND SPECIFICATIONS MUST BE KEPT ON THE JOB AT ALL TIMES AND NO CHANGES OR ALTERATIONS SHALL BE MADE EXCEPT BY THE BUILDING DIVISION.

THE STAMPING OF THIS PLAN AND SPECIFICATIONS SHALL NOT BE HELD TO PERMIT OR TO BE AN APPROVAL OF THE VIOLATION OF ANY PROVISIONS OF ANY CITY ORDINANCE OR STATE LAW. "REVIEWED FOR CODE COMPLIANCE."

*Mitchell Cook*

12/11/2025



#### KEYNOTES/LEGEND

- BRACED WALL LINE
- FOUNDATION PLAN DETAIL FOUND ON SHEET S3
- INDICATES CONCRETE FOOTING AREA

WALL BRACING SCHEDULE	
TYPE	MATERIAL
1	3/8" PLYWD <sup>2</sup> 6d NAILS; EDGES @ 6" O.C., FIELD NAIL @ 12" O.C.

- EXPANDED METAL OR WOVEN WIRE LATH STAPLED TO ALL STUDS, TOP AND BTM.
- STRUCTURAL PANEL SHEATHING TO BE USED ON ALL EXTERIOR SURFACES INCLUDING AREAS ABOVE AND BELOW OPENINGS.

#### WALL BRACING NOTES

- FOR THE PURPOSE OF DETERMINING THE AMOUNT AND LOCATION OF BRACING REQUIRED IN EACH STORY LEVEL OF A BUILDING, BRACED WALL LINES SHALL BE DESIGNATED AS STRAIGHT LINES IN THE BUILDING PLAN PLACED IN ACCORDANCE WITH THIS SECTION. (CRC602.10.1)
- THE LENGTH OF A BRACED WALL LINE SHALL BE THE DISTANCE BETWEEN ITS ENDS. THE END OF A BRACED WALL LINE SHALL BE THE INTERSECTION WITH A PERPENDICULAR BRACED WALL LINE, AN ANGLED BRACED WALL LINE AS PERMITTED IN SECTION R602.10.1.4 OR AN EXTERIOR WALL AS SHOWN IN FIGURE R602.10.1.1. (CRC602.10.1.1)
- EACH BRACED WALL LINE SHALL BE LOCATED SUCH THAT NO MORE THAN TWO-THIRDS OF THE REQUIRED BRACED WALL PANEL LENGTH IS LOCATED TO ONE SIDE OF THE BRACED WALL LINE. BRACED WALL PANELS SHALL BE PERMITTED TO BE OFFSET UP TO 4 FEET (1219 MM) FROM THE DESIGNATED BRACED WALL LINE. BRACED WALL PANELS PARALLEL TO A BRACED WALL LINE SHALL BE OFFSET NOT MORE THAN 4 FEET (1219 MM) FROM THE DESIGNATED BRACED WALL LINE LOCATION AS SHOWN IN FIGURE R602.10.1.1. EXTERIOR WALLS PARALLEL TO A BRACED WALL LINE SHALL BE OFFSET NOT MORE THAN 4 FEET (1219 MM) FROM THE DESIGNATED BRACED WALL LINE LOCATION AS SHOWN IN FIGURE R602.10.1.1. INTERIOR WALLS USED AS BRACING SHALL BE OFFSET NOT MORE THAN 4 FEET (1219 MM) FROM A BRACED WALL LINE THROUGH THE INTERIOR OF THE BUILDING AS SHOWN IN FIGURE R602.10.1.1. (CRC602.10.1.2)
- THE SPACING BETWEEN PARALLEL BRACED WALL LINES SHALL BE IN ACCORDANCE WITH TABLE R602.10.1.3. INTERMEDIATE BRACED WALL LINES THROUGH THE INTERIOR OF THE BUILDING SHALL BE PERMITTED. (CRC602.10.1.3)

TABLE R602.10.1.3  
BRACED WALL LINE SPACING

APPLICATION	CONDITION	BUILDING TYPE	BRACED WALL LINE SPACING CRITERIA	
			Maximum Spacing	Exception to Maximum Spacing
Wind bracing	Ultimate design wind speed 100 mph to < 140 mph	Detached, townhouse	60 feet	None
	SDC A - C	Detached		Use wind bracing
	SDC A - B	Townhouse		Use wind bracing
	SDC C	Townhouse	35 feet	Up to 50 feet when length of required bracing per Table R602.10.3(3) is adjusted in accordance with Table R602.10.3(4).
Seismic bracing	SDC D <sub>0</sub> , D <sub>1</sub> , D <sub>2</sub>	Detached, townhouses, one- and two-story only	25 feet	Up to 35 feet to allow for a single room not to exceed 900 square feet. Spacing of all other braced wall lines shall not exceed 25 feet.
	SDC D <sub>0</sub> , D <sub>1</sub> , D <sub>2</sub>	Detached, townhouse	25 feet	Up to 35 feet when length of required bracing per Table R602.10.3(3) is adjusted in accordance with Table R602.10.3(4).

For SI: 1 foot = 304.8 mm, 1 square foot = 0.0929 m<sup>2</sup>, 1 mile per hour = 0.447 m/s.

- BRACED WALL LINES WITH A LENGTH OF 16 FEET (4877 MM) OR LESS SHALL HAVE NOT LESS THAN TWO BRACED WALL PANELS OF ANY LENGTH OR ONE BRACED WALL PANEL EQUAL TO 48 INCHES (1219 MM) OR MORE. BRACED WALL LINES GREATER THAN 16 FEET (4877 MM) SHALL HAVE NOT LESS THAN TWO BRACED WALL PANELS. (CRC602.10.2.3)

- TABLE R602.10.3(1) AND THE APPLICABLE ADJUSTMENT FACTORS IN TABLE R602.10.2(2) (CRC602.10.3)

TABLE R602.10.3(3)  
BRACING REQUIREMENTS BASED ON SEISMIC DESIGN CATEGORY

Seismic Design Category	Story Location	Braced Wall Line Length (feet) <sup>a</sup>	MINIMUM TOTAL LENGTH (FEET) OF BRACED WALL PANELS REQUIRED ALONG EACH BRACED WALL LINE <sup>a,b</sup>				
			Method LIB <sup>d</sup>	Method GB	Methods DWB, SFB, PBS, PCP, HPS, CS-SFB <sup>e</sup>	Method WSP	Methods CS-WSP, CS-G, CS-PF <sup>f</sup>
D <sub>0</sub>	10	NP	2.8	2.8	1.8	1.6	
		NP	5.5	5.5	3.6	3.1	
		NP	8.3	8.3	5.4	4.6	
		NP	11.0	11.0	7.2	6.1	
		NP	13.8	13.8	9.0	7.7	
	20	NP	5.3	5.3	3.8	3.2	
		NP	10.5	10.5	7.5	6.4	
		NP	15.8	15.8	11.3	9.6	
		NP	21.0	21.0	15.0	12.8	
		NP	26.3	26.3	18.8	16.0	
	30	NP	7.3	7.3	5.3	4.5	
		NP	14.5	14.5	10.5	9.0	
		NP	21.8	21.8	15.8	13.4	
		NP	29.0	29.0	21.0	17.9	
		NP	36.3	36.3	26.3	22.3	

For SI: 1 inch = 25.4 mm, 1 foot = 304.8 mm, 1 pound per square foot = 0.0479 kPa.

NP = Not Permitted.

- Linear interpolation shall be permitted.
- Wall bracing lengths are based on a site class "D". Interpolation of bracing length between the  $S_{br}$  values associated with the seismic design categories shall be permitted when a site-specific  $S_{br}$  value is determined in accordance with Section 1613.2 of the California Building Code.
- Where the braced wall line length is greater than 50 feet, braced wall lines shall be permitted to be divided into shorter segments having lengths of 50 feet or less, and the amount of bracing within each segment shall be in accordance with this table.
- Method LIB shall have gypsum board fastened to not less than one side with nails or screws in accordance with Table R602.3(1) for exterior sheathing or Table R702.3.5 for interior gypsum board. Spacing of fasteners at panel edges shall not exceed 8 inches.
- Methods PFG and CS-SFB do not apply in Seismic Design Categories D<sub>0</sub>, D<sub>1</sub>, and D<sub>2</sub>.
- Where more than one bracing method is used, mixing methods shall be in accordance with Section R602.10.4.1.

FIGURE R602.10.7  
END CONDITIONS FOR BRACED WALL LINES WITH CONTINUOUS SHEATHING





FIGURE R602.10.5  
BRACED WALL PANELS WITH CONTINUOUS SHEATHING



DISCLAIMER:  
BY USING THESE STANDARD PLANS, THE USER AGREES TO RELEASE THE CITY OF HANFORD FROM ANY AND ALL CLAIMS, LIABILITIES, SUITS AND DEMANDS ON ACCOUNT OF ANY INJURY, DAMAGE, OR LOSS TO PERSONS OR PROPERTY, INCLUDING INJURY OR DEATH, OR ECONOMIC LOSSES, ARISING OUT OF THE USE OF THESE CONSTRUCTION DOCUMENTS. THE USE OF THESE PLANS DOES NOT ELIMINATE OR REDUCE THE USER'S RESPONSIBILITY TO VERIFY ANY AND ALL INFORMATION.



REVISIONS

PROJECT TITLE	CITY OF HANFORD - PRE-REVIEWED ADU PROGRAM
ADU SQFT	375
AGENCY	SJV REAP
SHEET DESCRIPTION	FOUNDATION PLAN
DATE	10/28/2024

DRAWING SCALE

BUILDING DIVISION


APPROVED = 1'

THIS SET OF PLANS AND SPECIFICATIONS MUST BE KEPT ON THE JOB AT ALL TIMES AND NO CHANGES OR ALTERATIONS SHALL BE MADE EXCEPT BY THE BUILDING DIVISION.

THE STAMPING OF THIS PLAN AND SPECIFICATIONS SHALL NOT BE HELD TO PERMIT OR TO BE AN APPROVAL OF THE VIOLATION OF ANY PROVISIONS OF ANY CITY ORDINANCE OR STATE LAW. "REVIEWED FOR CODE COMPLIANCE."

By: Mitchell Cook

12/11/2025



#### KEYNOTES

- (1) PRE-MFR. TRUSSES @ 24" O.C.
- (2) 15/32" APA RATED PLYWD OR OSB, P.I. 32/16, EDGE NAIL W/8D @ 6" O.C. & FIELD NAIL @ 6" O.C.
- (3) 6X8 D.F. # 2
- (4) TOP OF NON-BEARING, NON-BRACED WALL. SEE DETAIL 5.
- (5) SEE DETAIL 3 FOR END WALL TRUSS SHEAR TRANSFER DESIGN REQUIREMENT
- (6) LOCATION OF 12"x18" GABLE END VENT
- (7) LOCATION OF 5 1/2" x 22 1/2" ROOF TOP VENT
- (8) LOCATION OF RANGE HOOD VENT
- # FRAMING PLAN DETAIL FOUND ON SHEET S3

#### NOTES

1. TRUSS CALCULATIONS (FROM THE TRUSS MANUFACTURER) SHALL BE PROVIDED TO THE BUILDING DEPARTMENT PRIOR TO A REQUEST FOR ROOF AND SHEAR INSPECTION

#### ATTIC VENTILATION REQUIREMENTS

$$\frac{375 \text{ SQFT}}{150} \cdot 144 \text{ in}/\text{ft} = (360 \text{ in}^2)$$

#### PROVIDE:

$$2 - 12"\text{x}18" \text{ GABLE END VENT } (140 \text{ in}^2) = (280 \text{ in}^2)$$

$$1 - 5-1/2" \text{ x } 22-1/2" \text{ ROOF TOP VENT } (83 \text{ in}^2) = (83 \text{ in}^2)$$


$$\text{TOTAL PROVIDED: } = (363 \text{ in}^2)$$

These plans and documents have been reviewed for compliance with the applicable codes requirements of the jurisdiction. The stamping of these plans shall not be held to permit or be an approval of any violation of applicable codes and standards nor relieve the owner, design professional of record or contractor of compliance with applicable codes and standards.

ROD CARSEY CONSULTING & PLAN CHECK SERVICE

DISCLAIMER:  
BY USING THESE STANDARD PLANS, THE USER AGREES TO RELEASE THE CITY OF HANFORD FROM ANY AND ALL CLAIMS, LIABILITIES, SUITS AND DEMANDS ON ACCOUNT OF ANY INJURY, DAMAGE, OR LOSS TO PERSONS OR PROPERTY, ARISING OUT OF THE USE OF THESE CONSTRUCTION DOCUMENTS. THE USE OF THESE PLANS DOES NOT ELIMINATE OR REDUCE THE USER'S RESPONSIBILITY TO VERIFY ANY AND ALL INFORMATION.

**CITY OF HANFORD**



PROJECT TITLE	CITY OF HANFORD – PRE-REVIEWED ADU PROGRAM	
ADU SQFT	SHEET DESCRIPTION	ROOF FRAMING PLAN
AGENCY	S.J.V REAP	DATE
375		10/28/2024

375

DRAWING SCALE  
BUILDING DIVISION  
APPROVED

THIS SET OF PLANS AND SPECIFICATIONS  
MUST BE KEPT ON THE JOB AT ALL TIMES AND  
NO CHANGES OR ALTERATIONS SHALL BE  
MADE EXCEPT BY THE BUILDING DIVISION.


THE STAMPING OF THESE PLANS AND  
SPECIFICATIONS SHALL NOT BE HELD TO  
PERMIT OR TO BE AN APPROVAL OF THE  
VIOLATION OF ANY PROVISIONS OF ANY CITY  
ORDINANCE OR STATE LAW. "REVIEWED FOR  
CODE COMPLIANCE."

12/11/2025

12/11/2025

DISCLAIMER:  
BY USING THESE STANDARD PLANS, THE USER AGREES TO  
RELEASE THE CITY OF HANFORD FROM ANY AND ALL CLAIMS,  
LIABILITIES, SUITS AND DEMANDS ON ACCOUNT OF ANY  
INJURY, DAMAGE, OR LOSS TO PERSONS OR PROPERTY,  
OUT OF THE USE OF THESE CONSTRUCTION DOCUMENTS, ARISING  
OUT OF THE USE OF THESE PLANS DOES NOT ELIMINATE OR REDUCE THE  
USER'S RESPONSIBILITY TO VERIFY ANY AND ALL INFORMATION.

# CITY OF HANFORD



REVISIONS

PROJECT TITLE	CITY OF HANFORD - PRE-REVIEWED ADU PROGRAM		DETAILS		DATE	
AGENCY	S.JV REAP	PROGRAM	DETAILS	EXTERIOR	INTERIOR	10/28/2024
ADU SQFT	375					


DRAWING SCALE  
CITY OF HANFORD  
BUILDING DIVISION  
**APPROVED**

THIS SET OF PLANS AND SPECIFICATIONS  
MUST BE KEPT ON THE JOB AT ALL TIMES AND  
NO CHANGES OR ALTERATIONS SHALL BE  
MADE EXCEPT BY THE BUILDING DIVISION.


THE STAMPING OF THIS PLAN AND  
SPECIFICATIONS SHALL NOT BE HELD TO  
PERMIT OR TO BE AN APPROVAL OF THE  
VIOLATION OF ANY PROVISIONS OF ANY CITY  
ORDINANCE OR STATE LAW. "REVIEWED FOR  
CODE COMPLIANCE."

*Mitchell Cook*

12/11/2025




① EXTERIOR FOOTING  
N.T.S.




② NON-BEARING INTERIOR FOOTING  
N.T.S.


TENSION STRAP AT INTERIOR FACE  
OF WALL, STRAP ACROSS HEADER  
AND JAMB STUDS:  
SIMPSON MSTA 30 (2,050 lbs TENSION)




DERIVED FROM CRC  
FIGURE R602.10.4.2




④ EAVE DETAIL  
N.T.S.



⑤ NON-BRG., NON-BRACED WALL CONNECTION  
N.T.S.



⑥ GABLE END DETAIL  
N.T.S.



TYP. WALL FRAMING AT OPENING  
N.T.S.

These plans and documents have been reviewed  
for compliance with the applicable codes  
requirements of the jurisdiction. The stamping  
of these plans shall not be held to permit or be  
an approval of any violation of applicable codes  
and standards nor relieve the owner, design  
professional of record or contractor of  
compliance with applicable codes and standards

ROD CARSEY CONSULTING & PLAN CHECK  
SERVICE

CLEAR SPAN OF OPENING	HEADER SIZE NOTE 1		NUMBER OF CRIPPLES		NUMBER OF KING STUDS		NUMBER OF SILL PLATES	
	BEARING WALL	NON-BRG WALL	BRG WALL	NON-BRG WALL	EXTERIOR	INTERIOR	EXTERIOR	INTERIOR
UP TO 6'-0"	4 x 8	4 x 6	1	1	1	1	1	1

NOTES:


1. 4x HEADER SIZE SHOWN IS FOR 2x4 STUD WALL, REVISE TO 6x FOR 2x6 STUD WALLS AND 8x FOR 2x8 STUD WALLS.
2. DETAILS AND MEMBER SIZES ARE TYPICAL UNLESS OTHERWISE NOTED OR DETAILED.
3. NOTES AND MEMBER SIZES SHOWN ON FRAMING PLANS SHALL TAKE PRECEDENCE OVER SCHEDULE.

⑦ HEADER DETAIL  
N.T.S.

12/11/2025

DISCLAIMER:  
BY USING THESE STANDARD PLANS, THE USER AGREES TO  
RELEASE THE CITY OF HANFORD FROM ANY AND ALL CLAIMS,  
LIABILITIES, SUITS AND DEMANDS ON ACCOUNT OF ANY  
INJURY, DAMAGE, OR LOSS TO PERSONS OR PROPERTY,  
OUT OF THE USE OF THESE CONSTRUCTION DOCUMENTS. THE  
USER'S RESPONSIBILITY TO VERIFY ANY AND ALL INFORMATION.

# CITY OF HANFORD



REVISIONS

PROJECT TITLE	CITY OF HANFORD - PRE-REVIEWED ADU PROGRAM
AGENCY	S.J.V REAP

ADU SQFT

375

DRAWING SCALE

CITY OF HANFORD

BUILDING DIVISION


APPROVED

THIS SET OF PLANS AND SPECIFICATIONS  
MUST BE KEPT ON THE JOB AT ALL TIMES AND  
NO CHANGES OR ALTERATIONS SHALL BE  
MADE EXCEPT BY THE BUILDING DIVISION.


THE STAMPING OF THIS PLAN AND  
SPECIFICATIONS SHALL NOT BE HELD TO  
PERMIT OR TO BE AN APPROVAL OF THE  
VIOLATION OF ANY PROVISIONS OF ANY CITY  
ORDINANCE OR STATE LAW. "REVIEWED FOR  
CODE COMPLIANCE."

By *Mitchell Cook*


12/11/2025




8 1-HOUR FIRE RATED ASSEMBLY FOR STUCCO FINISH  
N.T.S.




9 1-HOUR FIRE RATED ASSEMBLY FOR  
ENGINEERED OR NATURAL WOOD SIDING  
N.T.S.




10 1-HOUR FIRE RATED ASSEMBLY FOR  
ENGINEERED OR NATURAL WOOD SIDING  
N.T.S.




11 1-HOUR FIRE RATED ASSEMBLY FOR  
FIBER CEMENT SIDING  
N.T.S.




12 1-HOUR FIRE RATED GABLE END FOR STUCCO FINISH  
N.T.S.



13 1-HOUR FIRE RATED GABLE END FOR ENGINEERED OR  
NATURAL WOOD SIDING  
N.T.S.



14 1-HOUR FIRE RATED GABLE END FOR ENGINEERED OR  
NATURAL WOOD SIDING  
N.T.S.



15 1-HOUR FIRE RATED GABLE END FOR FIBER CEMENT SIDING  
N.T.S.

These plans and documents have been reviewed  
for compliance with the applicable codes  
requirements of the jurisdiction. The stamping  
of these plans shall not be held to permit or be  
an approval of any violation of applicable codes  
and standards nor relieve the owner, design  
professional of record or contractor of  
compliance with applicable codes and standards

ROD CARSEY CONSULTING & PLAN CHECK  
SERVICE

12/11/2025

120/240V 1PH 3 WIRE 100 AMP  
MLO  
NEMA-1 FLUSH MOUNT 30 CK **PANEL SCHEDULE -PANEL 'A'**  
10KAIC #498

**ELECTRICAL LEGEND**

DUPLEX OUTLET	FAN AND LIGHT COMBINATION (HE LIGHT)
GFCI OUTLET	HIGH EFFICACY LIGHT FIXTURE
WEATHERPROOF GFCI OUTLET	HIGH EFFICACY RECESSED LIGHT
WALL SWITCH	GARBAGE DISPOSAL
GARBAGE DISPOSAL SWITCH	
VACANCY SENSOR	
SMOKE DETECTOR	
CARBON MONOXIDE ALARM	FAN & LIGHT COMBO

**SUB-PANEL & SWITCH GEAR FOR FUTURE BATTERY STORAGE** **N.T.S.**

CHANGE SERVICE TO 200 AMP 1-SINGLE PHASE 120/240V SOLAR READY PANEL. CONTACT YOUR LOCAL UTILITY PROVIDER

DESCRIPTION	CKT	OCPD	PHASE A	PHASE B	OCPD	CKT	DESCRIPTION
RECEPTACLES	1	20 AMP	1800	1300	15 AMP	2	LIGHTING
WASHER	3	20 AMP	1800	2700	30 AMP	4	DRYER
RANGE	5	40 AMP	3700	2700	30 AMP	6	DRYER
RANGE	7	40 AMP	3700	1350	20 AMP	8	KITCHEN APPLIANCE
KITCHEN APPLIANCE	9	20 AMP	1350	1800	20 AMP	10	DISH WASHER
RECEPTACLES	11	20 AMP	1800	1800	20 AMP	12	DISPOSAL
EF #1 AND EF #2	13	20 AMP	600	4000	50 AMP	14	COOK TOP
	15			4000	50 AMP	16	COOK TOP
WATER HEATER	17	30 AMP	2400	2400	30 AMP	18	FURNACE
WATER HEATER	19	30 AMP	2400	2400	30 AMP	20	FURNACE
SPACE	21					22	SPACE
SPACE	23					24	SPACE
SPACE	25					26	SPACE
SPACE	27					28	SPACE
SPACE	29					30	SPACE
SPACE	31					32	SPACE
SPACE	33					34	SPACE
SPACE	35					36	SPACE
SPACE	37					38	SPACE
SPACE	39					40	SPACE
SPACE	41					42	SPACE
TOTAL VA LOAD		14150	11650				
25% LCU/IML		3538	2913				
TOTAL LOAD		17688	14563				
TOTAL LOAD AMPS		64	53				

**SOLAR READY KEYNOTES #**

NOTE: SOLAR READY NOTES SHOWN TO DEMONSTRATE PLAN IS SOLAR READY. SEPARATE PERMIT AND FEES ARE REQUIRED. IF REQUIRED, CONTACT A PV/SOLAR PROVIDER FOR PLANS AND PERMITS.

1. THE MAIN ELECTRICAL SERVICE PANEL SHALL NOT BE OF A TYPE WITH A CENTER-FED MAIN CIRCUIT BREAKER AND SHALL INCLUDE RESERVED SPACE ALLOWING FOR INSTALLATION OF DOUBLE-POLE CIRCUIT BREAKERS FOR A FUTURE SOLAR PHOTOVOLTAIC SYSTEM. SUCH RESERVED SPACE SHALL BE POSITIONED AT THE OPPOSITE (LOAD) END FROM THE INPUT FEEDER OR MAIN CIRCUIT BREAKER LOCATION. THE RESERVED SPACE SHALL BE PERMANENTLY AND VISIBLY MARKED AS "FOR FUTURE SOLAR PHOTOVOLTAIC".
2. APPROVED MINIMUM 4-INCH SQUARE ELECTRICAL JUNCTION BOX LOCATED WITHIN 72 INCHES HORIZONTALLY AND 12 INCHES VERTICAL OF MAIN ELECTRICAL SERVICE PANEL.
3. MINIMUM 1 INCH DIAMETER LISTED ELECTRICAL METALLIC RACEWAY ORIGINATING AT READILY ACCESSIBLE ATTIC LOCATION WITH PROXIMITY TO SOLAR ZONE AREA AND TERMINATING AT THE REQUIRED ELECTRICAL JUNCTION BOX.
4. MINIMUM 1 INCH DIAMETER LISTED ELECTRICAL METALLIC RACEWAY ORIGINATING AT THE REQUIRED ELECTRICAL JUNCTION BOX AND TERMINATING AT THE MAIN ELECTRICAL SERVICE PANEL.
5. ELECTRICAL JUNCTION BOX AND SEGMENT OF METALLIC RACEWAY IN THE ATTIC SHALL BE PERMANENTLY AND VISIBLY MARKED AS "FOR FUTURE SOLAR PHOTOVOLTAIC".

**CLOTHES DRYER VENT NOTES**

1. 4" Ø DRYER VENT WITH MAXIMUM 14 FOOT COMBINED HORIZONTAL AND VERTICAL LENGTH WITH TWO 90 DEGREE ELBOWS.
2. SMALL APPLIANCE CIRCUIT LOAD IN EACH DWELLING UNIT, THE LOAD SHALL BE CALCULATED AT 1500 VOLT-AMPERES FOR EACH 2-WIRE SMALL APPLIANCE BRANCH CIRCUIT AS COVERED BY 2010.11(C)(1). WHERE THE LOAD IS SUBDIVIDED THROUGH TWO OR MORE FEEDERS, THE CALCULATED LOAD FOR EACH SHALL INCLUDE NOT LESS THAN 1500 VOLT-AMPERES FOR EACH 2-WIRE SMALL APPLIANCE BRANCH CIRCUIT. THESE LOADS SHALL BE PERMITTED TO BE INCLUDED WITH THE GENERAL LIGHTING LOAD AND SUBJECTED TO THE DEMAND FACTORS PROVIDED IN TABLE 220.42.
- 2.1. THE INDIVIDUAL BRANCH CIRCUIT PERMITTED BY 210.52(B)(1). EXCEPTION NO. 2, SHALL BE PERMITTED TO BE EXCLUDED FROM THE CALCULATION REQUIRED BY 220.52.
3. LAUNDRY CIRCUIT LOAD A LOAD OF NOT LESS THAN 1500 VOLT-AMPERES SHALL BE INCLUDED FOR EACH 2-WIRE LAUNDRY BRANCH CIRCUIT INSTALLED AS COVERED BY 210.11(C)(2). THIS LOAD SHALL BE SUBJECTED TO THE DEMAND FACTORS PROVIDED IN TABLE 220.42. [CEC 220.43(B)]
4. APPLIANCE LOAD-DWELLING UNITS IT SHALL BE PERMISSIBLE TO APPLY A DEMAND FACTOR OF 75 PERCENT TO THE NAMEPLATE RATING LOAD OF FOUR OR MORE APPLIANCES RATED  $\frac{1}{2}$  HP OR GREATER, OR 500 WATTS OR GREATER, THAT ARE FASTENED IN PLACE AND THAT ARE SERVED BY THE SAME FEEDER OR SERVICE IN A ONE-FAMILY, TWO-FAMILY, OR MULTIFAMILY DWELLING. THIS DEMAND FACTOR SHALL NOT APPLY TO: HOUSEHOLD ELECTRIC COOKING EQUIPMENT THAT IS FASTENED IN PLACE, CLOTHES DRYERS, SPACE HEATING EQUIPMENT, AND AIR-CONDITIONING EQUIPMENT. [CEC 220.53]
5. ELECTRIC CLOTHES DRYER THE LOAD FOR HOUSEHOLD ELECTRIC CLOTHES DRYERS IN A DWELLING UNIT SHALL BE EITHER 5,000 WATTS OR THE NAMEPLATE RATING, WHICHEVER IS LARGER, FOR EACH DRYER SERVED. THE USE OF THE DEMAND FACTORS IN TABLE 220.54 SHALL BE PERMITTED. WHERE TWO OR MORE SINGLE-PHASE DRYERS ARE SUPPLIED BY A 3-PHASE, 4-WIRE FEEDER OR SERVICE, THE TOTAL LOAD SHALL BE CALCULATED ON THE BASIS OF TWICE THE MAX. NUMBER CONNECTED BETWEEN ANY TWO PHASES. KILOWOLT-AMPERES SHALL BE CONSIDERED EQUIVALENT TO KILOWATTS FOR LOADS CALCULATED IN THIS SECTION.

**OUTLET NOTES**

1. RECEPTACLES SHALL BE INSTALLED SUCH THAT NO POINT MEASURED HORIZONTALLY ALONG THE FLOOR LINE OF ANY WALL SPACE IS MORE THAN 6 FEET FROM A RECEPTACLE OUTLET. [CEC 210.52(A)(1)]
2. GFCI OUTLETS. GROUND FAULT CIRCUIT INTERRUPTER (GFCI) OUTLETS ARE REQUIRED IN BATHROOMS, AT KITCHEN COUNTERTOPS, AT LAUNDRY AND WET BAR SINKS, IN GARAGES, IN CRAWLSPACES, IN UNFINISHED BASEMENTS, AND OUTDOORS. (CEC 210.8)
3. AFCI OUTLETS. ELECTRICAL CIRCUITS IN BEDROOMS, LIVING ROOMS, DINING ROOMS, DENS, CLOSETS, HALLWAYS, OR SIMILAR ROOMS MUST BE PROTECTED BY ARC FAULT CIRCUIT INTERRUPTERS (AFCI). (CEC 210.12)
4. RECEPTACLE OUTLETS SHALL BE LOCATED IN ONE OR MORE OF THE FOLLOWING:
  1. ON OR ABOVE COUNTERTOP OR WORK SURFACES: ON OR ABOVE, BUT NOT MORE THAN 20 INCHES ABOVE, THE COUNTERTOP OR WORK SURFACE.
  2. IN COUNTERTOP OR WORK SURFACES: RECEPTACLE OUTLET ASSEMBLIES LISTED FOR USE IN COUNTERTOPS OR WORK SURFACES SHALL BE PERMITTED TO BE INSTALLED IN COUNTERTOPS OR WORK SURFACES.
  3. BELOW COUNTERTOP OR WORK SURFACES: NOT MORE THAN 12 INCHES BELOW THE COUNTERTOP OR WORK SURFACE. RECEPTACLES INSTALLED BELOW A COUNTERTOP OR WORK SURFACE SHALL NOT BE LOCATED WHERE THE COUNTERTOP OR WORK SURFACE EXTENDS MORE THAN 6 INCHES BEYOND ITS SUPPORT BASE. [CEC 210.52(C)(3)]
5. BATHROOMS AT LEAST ONE RECEPTACLE OUTLET SHALL BE INSTALLED IN BATHROOMS WITHIN 3 FEET OF THE OUTSIDE EDGE OF EACH BASIN. THE RECEPTACLE OUTLET SHALL BE LOCATED ON A WALL OR PARTITION THAT IS ADJACENT TO THE BASIN OR BASIN COUNTERTOP, LOCATED ON THE COUNTERTOP, OR INSTALLED ON THE SIDE OR FACE OF THE BASIN CABINET. IN NO CASE SHALL THE RECEPTACLE BE LOCATED MORE THAN 12 INCHES BELOW THE TOP OF THE BASIN OR BASIN COUNTERTOP. RECEPTACLE OUTLET ASSEMBLIES LISTED FOR USE IN THE COUNTERTOPS SHALL BE PERMITTED TO BE INSTALLED IN THE COUNTERTOP. [CEC 210.52(D)]
6. OUTDOOR OUTLETS ALL EXTERIOR RECEPTACLES SHALL BE WP/GFCI PROTECTED. FOR A ONE-FAMILY DWELLING THAT IS AT GRADE LEVEL, AT LEAST ONE RECEPTACLE OUTLET READILY ACCESSIBLE FROM GRADE AND NOT MORE THAN 6  $\frac{1}{2}$  FEET ABOVE GRADE LEVEL SHALL BE INSTALLED AT THE FRONT AND BACK OF THE DWELLING. [210.52(E)(1)]
7. LAUNDRY AREAS IN DWELLING UNITS, AT LEAST ONE RECEPTACLE OUTLET SHALL BE INSTALLED IN AREAS DESIGNATED FOR THE INSTALLATION OF LAUNDRY EQUIPMENT. [210.52(F)]
8. GFCI OUTLETS. GROUND FAULT CIRCUIT INTERRUPTER (GFCI) OUTLETS ARE REQUIRED IN BATHROOMS, KITCHEN COUNTERTOPS, AT LAUNDRY AND WET BAR SINKS, IN GARAGES, IN CRAWLSPACES, IN UNFINISHED BASEMENTS, AND OUTDOORS. (CEC 210.8)
9. AFCI OUTLETS. ARC FAULT CIRCUIT INTERRUPTERS (AFCI) PROTECTION IS REQUIRED THROUGHOUT ALL 15 AND 20-AMP 120V CIRCUITRY THAT IS NOT GFCI PROTECTED. (CEC 210.12)

**REVISIONS**

PROJECT TITLE	CITY OF HANFORD - PRE-REVIEWED ADU PROGRAM	
ADU SQFT	375	
SHEET DESCRIPTION	ELECTRICAL PLAN	
AGENCY	SJV REAP	DATE 10/28/2024

**CITY OF HANFORD**

**DISCLAIMER:** BY USING THESE STANDARD PLANS, THE USER AGREES TO RELEASE THE CITY OF HANFORD FROM ANY AND ALL CLAIMS, LIABILITIES, SUITS AND DEMANDS ON ACCOUNT OF ANY INJURY, DAMAGE, OR LOSS TO PERSONS OR PROPERTY, ARISING OUT OF THE USE OF THESE CONSTRUCTION DOCUMENTS. THE USE OF THESE PLANS DOES NOT ELIMINATE OR REDUCE THE USER'S RESPONSIBILITY TO VERIFY ANY AND ALL INFORMATION.

**ROD CARSEY CONSULTING & PLAN CHECK SERVICE**

**375**

**DRAWING SCALE**

**BUILDING DIVISION APPROVED = 1'**

**THIS SET OF PLANS AND SPECIFICATIONS MUST BE KEPT ON THE JOB AT ALL TIMES AND NO CHANGES OR ALTERATIONS SHALL BE MADE EXCEPT BY THE BUILDING DIVISION.**

**THE STAMPING OF THIS PLAN AND SPECIFICATIONS SHALL NOT BE MADE TO PERMIT OR TO BE AN APPROVAL OF THE VIOLATION OF ANY PROVISIONS OF ANY CITY ORDINANCE OR STATE LAW. "REVIEWED FOR CODE COMPLIANCE."**

**BY Mitchell Cook**

**12/11/2025**

DISCLAIMER:  
BY USING THESE STANDARD PLANS, THE USER AGREES TO  
RELEASE THE CITY OF HANFORD FROM ANY AND ALL CLAIMS,  
LIABILITIES, SUITS AND DEMANDS ON ACCOUNT OF ANY  
INJURY, DAMAGE, OR LOSS TO PERSONS OR PROPERTY,  
ARISING OUT OF THE USE OF THESE CONSTRUCTION DOCUMENTS.  
THE USE OF THESE PLANS DOES NOT ELIMINATE OR REDUCE THE  
USER'S RESPONSIBILITY TO VERIFY ANY AND ALL INFORMATION.



REVISIONS

PROJECT TITLE	CITY OF HANFORD - PRE-REVIEWED ADU PROGRAM
ADU SQFT	375
STREET DESCRIPTION	PLUMBING PLAN
AGENCY	DATE
SJV REAP	10/28/2024

DRAWING SCALE  
1/2" = 1'

CITY OF HANFORD  
BUILDING DIVISION  
APPROVED

THIS SET OF PLANS AND SPECIFICATIONS  
MUST BE KEPT ON THE JOB AT ALL TIMES AND  
NO CHANGES OR ALTERATIONS SHALL BE  
MADE EXCEPT BY THE BUILDING DIVISION.

THE STAMPING OF THIS PLAN AND  
SPECIFICATIONS SHALL NOT BE HELD TO  
PERMIT OR TO BE AN APPROVAL OF THE  
VIOLATION OF ANY PROVISIONS OF ANY CITY  
ORDINANCE OR STATE LAW. "REVIEWED FOR  
CODE COMPLIANCE."

BY *Mitchell Cook*

12/11/2024




TABLE 610.4  
Fixture Unit Table for Determining Water Pipe and Meter Sizes

METER AND STREET SERVICE (inches)	BUILDING SUPPLY AND BRANCHES (inches)	MAXIMUM ALLOWABLE LENGTH (feet)														
		40	60	80	100	150	200	250	300	400	500	600	700	800	900	1000
PRESSURE RANGE — 30 to 45 psi <sup>1</sup>																
3/4	1 1/2 <sup>2</sup>	6	5	4	3	2	1	1	1	0	0	0	0	0	0	0
3/4	3/4	16	16	14	12	9	6	5	5	4	4	3	2	2	2	1
3/4	1	29	25	23	21	17	15	13	12	10	8	6	6	6	6	6
1	1	36	31	27	25	20	17	15	13	12	10	8	6	6	6	6
3/4	1 1/4	36	33	31	28	24	23	21	19	17	16	13	12	12	11	11
1	1 1/4	54	47	42	38	32	28	25	23	19	17	14	12	12	11	11
1 1/2	1 1/4	78	68	57	48	38	32	28	25	21	18	15	12	12	11	11
1	1 1/2	85	84	79	65	56	48	43	38	32	28	26	22	21	20	20
1 1/2	1 1/2	150	124	105	91	70	57	49	45	36	31	26	23	21	20	20
2	1 1/2	151	129	129	110	80	64	53	46	38	32	27	23	21	20	20
1	2	85	85	85	85	85	82	80	66	61	57	52	49	46	43	
1 1/2	2	220	205	190	176	155	138	127	120	104	85	70	61	57	54	51
2	2	370	327	292	265	217	185	164	147	124	96	70	61	57	54	51
2	2 1/2	445	418	390	370	330	300	280	265	240	220	198	175	158	143	133

For SI units: 1 inch = 25 mm, 1 foot = 304.8 mm, 1 pound-force per square inch = 6.8947 kPa

Notes:

<sup>1</sup> Available static pressure after head loss.

<sup>2</sup> Building supply, not less than 3/4 of an inch (20 mm) nominal size.

Fixture Unit Table

FIXTURES	QTY	COLD WATER		HOT WATER (COLD WATER VALUE x 0.75)	
		WSFU (EACH)	WSFU (EACH)	WSFU (EACH)	WSFU (EACH)
WATER CLOSET	1	2.5	2.5	0	0
LAVATORY	1	1	1	0.75	0.75
SINK	1	1.5	1.5	1.5	1.5
BATHTUB	1	4	4	3	3
DISHWASHER	1	1.5	1.5	1.5	1.5
CLOTHES WASHER	1	4	4	3	3
HOSE BIB	2	2.5	5	---	---
SUBTOTALS				9.75	
TOTAL				29.25	

### NOTES

ASSUMPTION: 3/4" MUNICIPAL WATER SERVICE

CONNECTION TO BE DETERMINED ON SITE

### 610.3 Quantity of Water

The quantity of water required to be supplied to every plumbing fixture shall be represented by fixture units, as shown in Table 610.3. Equivalent fixture values shown in Table 610.3 include both hot and cold water demand.

TABLE 610.3  
WATER SUPPLY FIXTURE UNITS (WSFU) AND MINIMUM FIXTURE BRANCH PIPE SIZES<sup>3</sup>

APPLIANCES, APPURTENANCES OR FIXTURES <sup>2</sup>	MINIMUM FIXTURE BRANCH PIPE SIZE <sup>1,4</sup> (inches)	PRIVATE	PUBLIC	ASSEMBLY <sup>5</sup>
Bathtub or Combination Bath/Shower (fill)	1/2	4.0	4.0	—
3/4 inch Bath/tub Fill Valve	3/4	10.0	10.0	—
Bidet	1/2	1.0	—	—
Clothes Washer	1/2	4.0	4.0	—
Dental Unit, cuspidor	1/2	—	1.0	—
Dishwasher, domestic	1/2	1.5	1.5	—
Drinking Fountain or Water Cooler	1/2	0.5	0.5	0.75
Hose Bibb	1/2	2.5	2.5	—
Hose Bibb, each additional <sup>6</sup>	1/2	1.0	1.0	—
Lavatory	1/2	1.0	1.0	1.0
Lawn Sprinkler, each head <sup>5</sup>	—	1.0	1.0	—
Mobilehome or Manufactured Home, each (minimum) <sup>9</sup>	—	6.0	—	—
Sinks	—	—	—	—
Bar	1/2	1.0	2.0	—
Clinical Faucet	1/2	—	3.0	—
Clinical Flushometer Valve with or without faucet	1	—	8.0	—
Kitchen, domestic with or without dishwasher	1/2	1.5	1.5	—
Laundry	1/2	1.5	1.5	—
Service or Mop Basin	1/2	1.5	3.0	—
Washup, each set of faucets	1/2	—	2.0	—
Shower, per head	1/2	2.0	2.0	—
Urinal, 1.0 GPF Flushometer Valve	2/4	See Footnote <sup>7</sup>	—	—
Urinal, greater than 1.0 GPF Flushometer Valve	3/4	See Footnote <sup>7</sup>	—	—
Urinal, flush tank	1/2	2.0	2.0	3.0
Urinal with Drain Cleansing Action	1/2	1.0	1.0	1.0
Wash Fountain, circular spray	3/4	—	4.0	—
Water Closet, 1.6 GPF Gravity Tank	1/2	2.5	2.5	3.5
Water Closet, 1.6 GPF Flushometer Tank	1/2	2.5	2.5	3.5
Water Closet, 1.6 GPF Flushometer Valve	1	See Footnote <sup>7</sup>	—	—
Water Closet, greater than 1.6 GPF Gravity Tank	1/2	3.0	5.5	7.0
Water Closet, greater than 1.6 GPF Flushometer Valve	1	See Footnote <sup>7</sup>	—	—

For SI units: 1 inch = 25 mm

Notes:

<sup>1</sup> Size of the cold branch pipe, or both the hot and cold branch pipes.

<sup>2</sup> Appliances, appurtenances, or fixtures not referenced in this table shall be permitted to be sized by reference to fixtures having a similar flow rate and frequency of use.

<sup>3</sup> The listed fixture unit values represent their load on the cold water supply. The separate cold water and hot water fixture unit value for fixtures having both hot and cold water connections shall be permitted to be each taken as three-quarter of the listed total value of the fixture.

<sup>4</sup> The listed minimum supply branch pipe sizes for individual fixtures are the nominal (L.D.) pipe size.

<sup>5</sup> For fixtures or supply connections likely to impose continuous flow demands, determine the required flow in gallons per minute (gpm), and add it separately to the demand in gpm (L/s) for the distribution system or portions thereof.

<sup>6</sup> Assembly (Public Use) (See Table 422.1).

<sup>7</sup> Where sizing flushometer systems, see Section 610.10.

<sup>8</sup> Reduced fixture unit loading for additional hose bibs is



California

# 2022 CALIFORNIA GREEN BUILDING STANDARDS CODE

## RESIDENTIAL MANDATORY MEASURES, SHEET 1 (January 2023)

Y = YES  
N/A = NOT APPLICABLE  
RESPON. PARTY = RESPONSIBLE PARTY (ie: ARCHITECT, ENGINEER, OWNER, CONTRACTOR, INSPECTOR ETC.)

<b>CHAPTER 3</b> <b>GREEN BUILDING</b> <b>SECTION 301 GENERAL</b>		<b>4.106.4.2 New multifamily developments, hotels and motels and new residential parking facilities.</b> Where a service panel or subpanel serving a new residential parking facility, before and after, shall meet the requirements of Sections 4.106.4.2.1 and 4.106.4.2.2. Calculations for spaces shall be rounded up to the nearest whole number. A parking space served by electric vehicle supply equipment or designed as a future EV charging space shall count as at least one standard automobile parking space only for the purpose of complying with any applicable minimum parking space requirements established by a local jurisdiction. See Vehicle Code Section 22511.2 for further details.		<b>4.106.4.2.4 Identification.</b> The service panel or subpanel circuit directory shall identify the overcurrent protective device space(s) reserved for future EV charging purposes as "EV CAPABLE" in accordance with the California Electrical Code.		<b>4.304 OUTDOOR WATER USE</b> <b>4.304.1 OUTDOOR POTABLE WATER USE IN LANDSCAPE AREAS.</b> Residential developments shall comply with a local water efficient landscape ordinance or the current California Department of Water Resources' Model Water Efficient Landscape Ordinance (MWELO), whichever is more stringent.	
<b>301.1 SCOPE.</b> Buildings shall be designed to include the green building measures specified as mandatory in the application checklists contained in this code. Voluntary green building measures are also included in the application checklists and may be included in the design and construction of structures covered by this code, but are not required unless adopted by a city, county, or city and county as specified in Section 101.7.		<b>4.106.4.2.5 Electric Vehicle Ready Space Signage.</b> Electric vehicle ready spaces shall be identified by signage or pavement markings, in compliance with Caltrans Traffic Operations Policy Directive 13-01 (Zero Emission Vehicle Signs and Pavement Markings) or its successor(s).		<b>4.106.4.3 Electric vehicle charging for additions and alterations of parking facilities serving existing multifamily buildings.</b> When new parking facilities are added, or electrical systems or lighting of existing parking facilities are added or altered and the work requires a building permit, ten (10) percent of the total number of parking spaces added or altered shall be electric vehicle charging spaces (EV spaces) capable of supporting future Level 2 EVSE. Notes: 1. Construction documents are intended to demonstrate the project's capability and capacity for facilitating future EV charging. 2. There is no requirement for EV spaces to be constructed or available until EV chargers are installed for use.		<b>4.304.2 MATERIA CONSERVATION AND RESOURCE EFFICIENCY</b>	
<b>301.1.1 Additions and alterations.</b> The mandatory provisions of Chapter 4 shall be applied to additions and alterations of existing residential buildings where the addition or alteration increases the building's conditioned area, volume, or size. The requirements shall apply only to and/or within the specific area of the addition or alteration.		<b>4.106.4.4 Multifamily developments projects with less than 20 dwelling units; and hotels and motels with less than 20 sleeping units or guest rooms.</b> The number of dwelling units, sleeping units or guest rooms shall be based on all buildings on a project site subject to this section.		<b>4.106.4.3.1 Water Closets.</b> The effective flush volume of all water closets shall not exceed 1.28 gallons per flush. Tank-type water closets shall be certified to the performance criteria of the U.S. EPA WaterSense Specification for Tank-type Toilets.		<b>4.406 ENHANCED DURABILITY AND REDUCED MAINTENANCE</b>	
<b>301.1.2 Additional additions or alterations.</b> The mandatory provision of Section 4.106.4.2 may apply to additions or alterations of existing multifamily buildings. See Section 4.106.4.3 for application.		<b>4.106.4.4.1 Water Conservation Plumbing Fixtures and Fittings.</b> Plumbing fixtures (water closets and urinals) and fittings (faucets and showerheads) shall comply with the sections 4.303.1.1, 4.303.1.2, 4.303.1.3, and 4.303.4.4.		<b>4.406.1 RODENT PROOFING.</b> Animal species around pipes, electric cables, conduits or other openings in soleplate plates at exterior walls shall be protected against the passage of rodents by closing such openings with cement mortar, concrete masonry or a similar method acceptable to the enforcing agency.			
<b>301.1.3 Note:</b> Repairs including, but not limited to, resurfacing, restriping and repairing or maintaining existing lighting fixtures are not considered alterations for the purpose of this section.		<b>4.106.4.4.2 Urinals.</b> The effective flush volume of wall mounted urinals shall not exceed 0.125 gallons per flush. The effective flush volume of all other urinals shall not exceed 0.5 gallons per flush.		<b>4.408 CONSTRUCTION WASTE REDUCTION, DISPOSAL AND RECYCLING</b>			
<b>301.1.4 Note:</b> On and after January 1, 2014, residential buildings undergoing permitted alterations, additions, or improvements shall replace non-compliant plumbing fixtures with water conserving plumbing fixtures. Plumbing fixture replacement is required prior to issuance of a certificate of final completion, certificate of occupancy or final permit approval by the local building department. See Civil Code Section 1101.1, et seq., for the definition of a noncompliant plumbing fixture, types of residential buildings affected and other important enactment dates.		<b>4.106.4.4.3 Showerheads.</b> Showerheads shall have a maximum flow rate of not more than 1.8 gallons per minute at 80 psi. Showerheads shall be certified to the performance criteria of the U.S. EPA 4.303.1.3.1 Single Showerhead Specification for Showerheads.		<b>4.408.1 CONSTRUCTION WASTE MANAGEMENT.</b> Recycle and/or salvage for reuse a minimum of 65 percent of the non-hazardous construction and demolition waste in accordance with either Section 4.408.2, 4.408.3, or 4.408.4, or meet a more stringent local construction and demolition waste management ordinance.			
<b>301.2 LOW-RISE AND HIGH-RISE RESIDENTIAL BUILDINGS.</b> [HCD] The provisions of individual sections of CALGreen may apply to either low-rise residential buildings high-rise residential buildings, or both. Individual sections will be designated by banners to indicate where the section applies specifically to low-rise (LR) or high-rise (HR). When the section applies to both low-rise and high-rise buildings, no banner will be used.		<b>4.106.4.4.4 Kitchen Faucets.</b> The maximum flow rate of kitchen faucets shall not exceed 1.8 gallons per minute at 80 psi. Kitchen faucets may temporarily increase the flow above the maximum rate, but not to exceed 2.2 gallons per minute at 60 psi, and must default to a maximum flow rate of 1.8 gallons per minute at 60 psi.		<b>4.408.2 WASTE MANAGEMENT COMPANY.</b> Utilize a waste management company, approved by the enforcing agency, which can provide verifiable documentation that the percentage of construction and demolition waste material diverted from the landfill complies with Section 4.408.4.			
<b>SECTION 302 MIXED OCCUPANCY BUILDINGS</b>		<b>4.106.4.4.5 Metering Faucets.</b> Metering faucets when installed in residential buildings shall not deliver more than 0.2 gallons per cycle.		<b>4.408.3 WASTE STREAM REDUCTION ALTERNATIVE [LR].</b> Projects that generate a total combined weight of construction and demolition waste disposed in landfills, which do not exceed 3.4 lbs./sq.ft. of the building area, shall meet the minimum 65% construction waste reduction requirement in Section 4.408.1.			
<b>302.1 MIXED OCCUPANCY BUILDINGS.</b> In mixed occupancy buildings, each portion of a building shall comply with the specific green building measures applicable to each specific occupancy.		<b>4.106.4.4.6 Rod Garsey Consulting &amp; Plan Check.</b> The stamping, the combined flow rate of all the showerheads and/or other shower outlets controlled by a single valve shall not exceed 1.8 gallons per minute at 80 psi, or the shower shall be designed to only allow one shower outlet to be in operation at a time.		<b>4.408.4 WASTE STREAM REDUCTION ALTERNATIVE.</b> Projects that generate a total combined weight of construction and demolition waste disposed in landfills, which do not exceed 2 pounds per square foot of the building area, shall meet the minimum 65% construction waste reduction requirement in Section 4.408.1.			
<b>302.1.1 Exceptions:</b>		<b>4.106.4.4.7 Residential Lavatory Faucets.</b> The maximum flow rate of residential lavatory faucets shall not exceed 1.2 gallons per minute at 60 psi. The minimum flow rate of residential lavatory faucets shall not exceed 0.8 gallons per minute at 60 psi.		<b>4.408.5 DOCUMENTATION.</b> Documentation shall be provided to the enforcing agency which demonstrates compliance with Section 4.408.2, items 1 through 5, Section 4.408.3 or Section 4.408.4.			
<b>302.1.2 [HCD] Accessory structures and accessory occupancies serving residential buildings shall comply with Chapter 4 and Appendix A4, as applicable.</b>		<b>4.106.4.4.8 Lavatory Faucets in Common and Public Use Areas.</b> The maximum flow rate of lavatory faucets installed in common and public use areas (outside of dwellings or sleeping units) in residential buildings shall not exceed 0.5 gallons per minute at 60 psi.		<b>Notes:</b>			
<b>302.1.3 [HCD] For purposes of CALGreen, live/work units, complying with Section 419 of the California Building Code, shall not be considered mixed occupancies. Live/Work units shall comply with Chapter 4 and Appendix A4, as applicable.</b>		<b>4.106.4.4.9 Metering Faucets.</b> Metering faucets when installed in residential buildings shall not deliver more than 0.2 gallons per cycle.		<b>1. Sample forms found in "A Guide to the California Green Building Standards Code (Residential)" located at <a href="http://www.hcd.ca.gov/CALGreen.html">www.hcd.ca.gov/CALGreen.html</a> may be used to assist in documenting compliance with this section.</b>			
<b>DIVISION 4.1 PLANNING AND DESIGN</b>		<b>4.106.4.4.10 Kitchen Faucets.</b> The maximum flow rate of kitchen faucets shall not exceed 1.8 gallons per minute at 60 psi. Kitchen faucets may temporarily increase the flow above the maximum rate, but not to exceed 2.2 gallons per minute at 60 psi, and must default to a maximum flow rate of 1.8 gallons per minute at 60 psi.		<b>2. Mixed construction and demolition debris (C &amp; D) products can be located at the California Department of Resources Recycling and Recovery (CalRecycle).</b>			
<b>ABBREVIATION DEFINITIONS:</b>		<b>4.106.4.4.11 Rod Garsey Consulting &amp; Plan Check.</b> The stamping, the combined flow rate of all the showerheads and/or other shower outlets controlled by a single valve shall not exceed 1.8 gallons per minute at 80 psi, or the shower shall be designed to only allow one shower outlet to be in operation at a time.		<b>4.410 BUILDING MAINTENANCE AND OPERATION</b>			
<b>HCD</b> Department of Housing and Community Development		<b>4.106.4.4.12 Residential Lavatory Faucets.</b> The maximum flow rate of residential lavatory faucets shall not exceed 1.2 gallons per minute at 60 psi. The minimum flow rate of residential lavatory faucets shall not exceed 0.8 gallons per minute at 60 psi.		<b>4.410.1 OPERATION AND MAINTENANCE MANUAL.</b> At the time of final inspection, a manual, compact disc, web-based resource or other media acceptable to the enforcing agency which includes all of the following shall be placed in the building:			
<b>BSC</b> California Building Standards Commission		<b>4.106.4.4.13 Lavatory Faucets in Common and Public Use Areas.</b> The maximum flow rate of lavatory faucets installed in common and public use areas (outside of dwellings or sleeping units) in residential buildings shall not exceed 0.5 gallons per minute at 60 psi.		<b>1. Directions to the owner or occupant that the manual shall remain with the building throughout the life cycle of the structure.</b>			
<b>DSA-SS</b> Division of the State Architect, Structural Safety		<b>4.106.4.4.14 Metering Faucets.</b> Metering faucets when installed in residential buildings shall not deliver more than 0.2 gallons per cycle.		<b>2. Operation and maintenance instructions for the following:</b>			
<b>OSHPD</b> Office of Statewide Health Planning and Development		<b>4.106.4.4.15 Kitchen Faucets.</b> The maximum flow rate of kitchen faucets shall not exceed 1.8 gallons per minute at 60 psi. Kitchen faucets may temporarily increase the flow above the maximum rate, but not to exceed 2.2 gallons per minute at 60 psi, and must default to a maximum flow rate of 1.8 gallons per minute at 60 psi.		<b>a. Equipment and appliances, including water-saving devices and systems, HVAC systems, photovoltaic systems, electric vehicle chargers, water-heating systems and other major equipment and equipment.</b>			
<b>LR</b> Low Rise		<b>4.106.4.4.16 Rod Garsey Consulting &amp; Plan Check.</b> The stamping, the combined flow rate of all the showerheads and/or other shower outlets controlled by a single valve shall not exceed 1.8 gallons per minute at 80 psi, or the shower shall be designed to only allow one shower outlet to be in operation at a time.		<b>b. Roof and drain coverage, including gutters and downspouts.</b>			
<b>HR</b> High Rise		<b>4.106.4.4.17 Residential Lavatory Faucets.</b> The maximum flow rate of residential lavatory faucets shall not exceed 1.2 gallons per minute at 60 psi. The minimum flow rate of residential lavatory faucets shall not exceed 0.8 gallons per minute at 60 psi.		<b>c. Space conditioning systems, including condensers and air filters.</b>			
<b>AA</b> Additions and Alterations		<b>4.106.4.4.18 Lavatory Faucets in Common and Public Use Areas.</b> The maximum flow rate of lavatory faucets installed in common and public use areas (outside of dwellings or sleeping units) in residential buildings shall not exceed 0.5 gallons per minute at 60 psi.		<b>d. Landscape irrigation systems.</b>			
<b>N</b> New		<b>4.106.4.4.19 Metering Faucets.</b> Metering faucets when installed in residential buildings shall not deliver more than 0.2 gallons per cycle.		<b>e. Water reuse systems.</b>			
<b>CHAPTER 4</b> <b>RESIDENTIAL MANDATORY MEASURES</b>		<b>4.106.4.4.20 Rod Garsey Consulting &amp; Plan Check.</b> The stamping, the combined flow rate of all the showerheads and/or other shower outlets controlled by a single valve shall not exceed 1.8 gallons per minute at 80 psi, or the shower shall be designed to only allow one shower outlet to be in operation at a time.		<b>3. Information from local utility, water and waste recovery providers on methods to further reduce water use, including water reuse and recycling.</b>			
<b>SECTION 4.102 DEFINITIONS</b>		<b>4.106.4.4.21 Residential Lavatory Faucets.</b> The maximum flow rate of residential lavatory faucets shall not exceed 1.2 gallons per minute at 60 psi. The minimum flow rate of residential lavatory faucets shall not exceed 0.8 gallons per minute at 60 psi.		<b>4. Public transportation and/or cycling options available in the area.</b>			
<b>4.102.1 DEFINITIONS</b>		<b>4.106.4.4.22 Lavatory Faucets in Common and Public Use Areas.</b> The maximum flow rate of lavatory faucets installed in common and public use areas (outside of dwellings or sleeping units) in residential buildings shall not exceed 0.5 gallons per minute at 60 psi.		<b>5. Educational material on the positive impacts of an interior relative humidity level in that range and what methods an occupant may use to maintain the relative humidity level in that range.</b>			
<b>The following terms are defined in Chapter 2 (and are included here for reference)</b>		<b>4.106.4.4.23 Rod Garsey Consulting &amp; Plan Check.</b> The stamping, the combined flow rate of all the showerheads and/or other shower outlets controlled by a single valve shall not exceed 1.8 gallons per minute at 80 psi, or the shower shall be designed to only allow one shower outlet to be in operation at a time.		<b>6. Information about water-conserving landscape and irrigation design and controllers which conserve water.</b>			
<b>FRENCH DRAIN.</b> A trench, hole or other depressed area loosely filled with rock, gravel, fragments of brick or similar pervious material used to collect or channel drainage or runoff water.		<b>4.106.4.4.24 Residential Lavatory Faucets.</b> The maximum flow rate of residential lavatory faucets shall not exceed 1.2 gallons per minute at 60 psi. The minimum flow rate of residential lavatory faucets shall not exceed 0.8 gallons per minute at 60 psi.		<b>7. Instructions for maintaining gutters and downspouts and the importance of diverting water at least 5 feet away from the foundation.</b>			
<b>WATTLES.</b> Wattles are used to reduce sediment in runoff. Wattles are often constructed of natural plant materials such as hay, straw or similar material shaped in the form of tubes and placed on a downflow slope. Wattles are also used for perimeter and inlet controls.		<b>4.106.4.4.25 Lavatory Faucets in Common and Public Use Areas.</b> The maximum flow rate of lavatory faucets installed in common and public use areas (outside of dwellings or sleeping units) in residential buildings shall not exceed 0.5 gallons per minute at 60 psi.		<b>8. Information on required routine maintenance measures, including, but not limited to, caulking, painting, grading around the building, etc.</b>			
<b>4.106.1 SITE DEVELOPMENT</b>		<b>4.106.4.4.26 Rod Garsey Consulting &amp; Plan Check.</b> The stamping, the combined flow rate of all the showerheads and/or other shower outlets controlled by a single valve shall not exceed 1.8 gallons per minute at 80 psi, or the shower shall be designed to only allow one shower outlet to be in operation at a time.		<b>9. Information about state solar energy and incentive programs available.</b>			
<b>4.106.1.1 GENERAL.</b> Preservation and use of available natural resources shall be accomplished through evaluation and careful planning to minimize negative effects on the site and adjacent areas. Preservation of slopes, management of storm water drainage and erosion controls shall comply with this section.		<b>4.106.4.4.27 Residential Lavatory Faucets.</b> The maximum flow rate of residential lavatory faucets shall not exceed 1.2 gallons per minute at 60 psi. The minimum flow rate of residential lavatory faucets shall not exceed 0.8 gallons per minute at 60 psi.		<b>10. A copy of all special inspections required by the enforcing agency or this code.</b>			
<b>4.106.2 STORM WATER DRAINAGE AND RETENTION DURING CONSTRUCTION.</b> Projects which disturb less than one acre of soil and are not part of a larger common plan of development in which total disturbs one acre or more, shall manage storm water drainage during construction. In order to manage storm water drainage during construction, one or more of the following measures shall be implemented to prevent flooding of adjacent property, prevent erosion and retain soil runoff on the site.		<b>4.106.4.4.28 Residential Lavatory Faucets.</b> The maximum flow rate of residential lavatory faucets shall not exceed 1.2 gallons per minute at 60 psi. The minimum flow rate of residential lavatory faucets shall not exceed 0.8 gallons per minute at 60 psi.		<b>11. Information from the Department of Forestry and Fire Protection on maintenance of defensible space around residential structures.</b>			
<b>4.106.2.1 General.</b> Where storm water is conveyed to a public drainage system, collection point, gutter or similar disposal method, water shall be filtered by use of a barrier system, wattle or other method approved by the enforcing agency.		<b>4.106.4.4.29 Rod Garsey Consulting &amp; Plan Check.</b> The stamping, the combined flow rate of all the showerheads and/or other shower outlets controlled by a single valve shall not exceed 1.8 gallons per minute at 80 psi, or the shower shall be designed to only allow one shower outlet to be in operation at a time.		<b>12. Information and/or drawings identifying the location of grab bar reinforcements.</b>			
<b>4.106.2.2 Storm Water Drainage and Retention During Construction.</b> Projects which disturb less than one acre of soil and are not part of a larger common plan of development in which total disturbs one acre or more, shall manage storm water drainage during construction. In order to manage storm water drainage during construction, one or more of the following measures shall be implemented to prevent flooding of adjacent property, prevent erosion and retain soil runoff on the site.		<b>4.106.4.4.30 Residential Lavatory Faucets.</b> The maximum flow rate of residential lavatory faucets shall not exceed 1.2 gallons per minute at 60 psi. The minimum flow rate of residential lavatory faucets shall not exceed 0.8 gallons per minute at 60 psi.		<b>4.412 RECYCLING BY OCCUPANTS.</b> Where 5 or more multifamily dwelling units are constructed on a building site, provide readily accessible area(s) that serves all buildings on the site and are identified for the depositing, storage and collection of non-hazardous materials for recycling, including (at a minimum) paper, corrugated cardboard, glass, plastics, organic waste, and metals, or meet a lawfully enacted local recycling ordinance, if more restrictive.			
<b>4.106.2.3 Grading and Paving.</b> Construction plans shall indicate how the site grading or drainage system will manage all surface water flows to keep water from entering buildings. Examples of methods to manage surface water include, but are not limited to, the following:		<b>4.106.4.4.31 Residential Lavatory Faucets.</b> The maximum flow rate of residential lavatory faucets shall not exceed 1.2 gallons per minute at 60 psi. The minimum flow rate of residential lavatory faucets shall not exceed 0.8 gallons per minute at 60 psi.		<b>Exception:</b> Residential units are required to accommodate a dedicated 208/240-volt branch circuit. The raceway shall not be less than trade size 1 (nominal 1-inch inside diameter). The raceway shall originate at the main service or subpanel and shall terminate into a listed cabinet, box or enclosure in close proximity to the proposed location of an EV charger. Raceways are required to be continuous at enclosed, inaccessible or concealed areas and spaces. The service panel and/or subpanel shall provide capacity to install a 40-ampere 208/240-volt minimum dedicated branch circuit and space(s) reserved to permit installation of a branch circuit overcurrent protective device.			
<b>4.106.2.4 Electric vehicle (EV) charging for new construction.</b> New construction shall comply with Sections 4.106.4.1 or 4.106.4.2 to facilitate future installation and use of EV chargers. Electric vehicle supply equipment (EVSE) shall be installed in accordance with the California Electrical Code, Article 625.		<b>4.106.4.4.32 Residential Lavatory Faucets.</b> The maximum flow rate of residential lavatory faucets shall not exceed 1.2 gallons per minute at 60 psi. The minimum flow rate of residential lavatory faucets shall not exceed 0.8 gallons per minute at 60 psi.		<b>Exception:</b> A raceway is not required if a minimum 40-ampere 208/240-volt dedicated EV branch circuit is installed in close proximity to the location or the proposed location of the EV space at the time of original construction in accordance with the California Electrical Code.			
<b>4.106.2.5 Exceptions:</b>		<b>4.106.4.4.33 Residential Lavatory Faucets.</b> The maximum flow rate of residential lavatory faucets shall not exceed 1.2 gallons per minute at 60 psi. The minimum flow rate of residential lavatory faucets shall not exceed 0.8 gallons per minute at 60 psi.		<b>4.413.2 Submitters for multifamily buildings and dwelling units in mixed-used residential/commercial buildings.</b> Submitters shall be installed to measure water usage of individual rental dwelling units in accordance with the California Plumbing Code.			
<b>4.106.2.6 Rod Garsey Consulting &amp; Plan Check.</b>		<b>4.106.4.4.34 Residential Lavatory Faucets.</b> The maximum flow rate of residential lavatory faucets shall not exceed 1.2 gallons per minute at 60 psi. The minimum flow rate of residential lavatory faucets shall not exceed 0.8 gallons per minute at 60 psi.		<b>4.413.3 Standards for plumbing fixtures and fittings.</b> Plumbing fixtures and fittings shall be installed in accordance with the California Plumbing Code, and shall meet the applicable standards referenced in Table 1701.1 of the California Plumbing Code.			
<b>4.106.2.7 Rod Garsey Consulting &amp; Plan Check.</b>		<b>4.106.4.4.35 Residential Lavatory Faucets.</b> The maximum flow rate of residential lavatory faucets shall not exceed 1.2 gallons per minute at 60 psi. The minimum flow rate of residential lavatory faucets shall not exceed 0.8 gallons per minute at 60 psi.		<b>NOTE:</b> THIS TABLE COMPILES THE DATA IN SECTION 4.303.1, AND IS INCLUDED AS A CONVENIENCE FOR THE USER.			
<b>4.106.2.8 Rod Garsey Consulting &amp; Plan Check.</b>		<b>4.106.4.4.36 Residential Lavatory Faucets.</b> The maximum flow rate of residential lavatory faucets shall not exceed 1.2 gallons per minute at 60 psi. The minimum flow rate of residential lavatory faucets shall not exceed 0.8 gallons per minute at 60 psi.		<b>4.414.1 RECYCLING BY OCCUPANTS.</b> Where 5 or more multifamily dwelling units are constructed on a building site, provide readily accessible area(s) that serves all buildings on the site and are identified for the depositing, storage and collection of non-hazardous materials for recycling, including (at a minimum) paper, corrugated cardboard, glass, plastics, organic waste, and metals, or meet a lawfully enacted local recycling ordinance, if more restrictive			



California

# 2022 CALIFORNIA GREEN BUILDING STANDARDS CODE

## RESIDENTIAL MANDATORY MEASURES, SHEET 2 (January 2023)

Y = YES  
N/A = NOT APPLICABLE  
RESPON. PARTY = RESPONSIBLE PARTY (i.e. ARCHITECT, ENGINEER, OWNER, CONTRACTOR, INSPECTOR ETC.)

Y	N/A	RESPON. PARTY		
<b>MAXIMUM INCREMENTAL REACTIVITY (MIR).</b> The maximum change in weight of ozone formed by adding a compound to the "Base Residue Organic Gas (ROG) Mixture" per weight of compound added, expressed to hundreds of a gram (g O <sub>3</sub> /g ROG). Note: MIR values for individual compounds and hydrocarbon solvents are specified in CCR, Title 17, Sections 94700 and 94701.				
<b>MOISTURE CONTENT.</b> The weight of the water in wood expressed in percentage of the weight of the oven-dry wood.				
<b>PRODUCT-WEIGHTED MIR (PWWMR).</b> The sum of all weighted-MIR for all ingredients in a product subject to this article. The PWWMR is the total product reactivity expressed to hundreds of a gram of ozone formed per gram of product (excluding container and packaging). Note: PWWMR is calculated according to equations found in CCR, Title 17, Section 94521 (a).				
<b>REACTIVE ORGANIC COMPOUND (ROC).</b> Any compound that has the potential, once emitted, to contribute to ozone formation in the troposphere.				
<b>VOC.</b> A volatile organic compound (VOC) broadly defined as a chemical compound based on carbon chains or rings with vapor pressure greater than 0.1 millimeters of mercury at room temperature. These compounds typically contain hydrogen and may contain oxygen, nitrogen and other elements. See CCR Title 17, Section 94508(a).				
<b>4.503 FIREPLACES</b>				
4.503.1 <b>GENERAL.</b> Any installed gas fireplace shall be a direct-vent sealed-combustion type. Any installed woodstove or pellet stove shall comply with U.S. EPA New Source Performance Standards (NSPS) emission limits as applicable, and shall have a permanent label indicating they are certified to meet the emission limits. Woodstoves, pellet stoves and fireplaces shall also comply with applicable local ordinances.				
<b>4.504 POLLUTANT CONTROL</b>				
4.504.1 <b>COVERING OF DUCT OPENINGS &amp; PROTECTION OF MECHANICAL EQUIPMENT DURING CONSTRUCTION.</b> At the time of rough installation, during storage on the construction site and until final startup of the heating, cooling and ventilating equipment, all duct and other related air distribution component openings shall be covered with tape, plastic, sheet metal or other methods acceptable to the enforcing agency to reduce the amount of water, dust or debris which may enter the system.				
4.504.2 <b>FINISH MATERIAL POLLUTANT CONTROL.</b> Finish materials shall comply with this section.				
4.504.2.1 <b>Adhesives, Sealants and Caulks.</b> Adhesives, sealant and caulk used on the project shall meet the requirements of the following standards unless more stringent local or regional air pollution or air quality management district rules apply:				
1. Adhesives, adhesive bonding primers, adhesive primers, sealants, sealant primers and caulk shall comply with local or regional air pollution control or air quality management district rules where applicable or SCAGMD Rule 1168 VOC limits, as shown in Table 4.504.1 or 4.504.2, as applicable. Such products also shall comply with the Rule 1168 prohibition on the use of certain toxic compounds (chloroform, ethylene dichloride, methylene chloride, perchloroethylene and trichloroethylene), except for aerosol products, as specified in Subsection 2 below.				
2. Aerosol adhesives, and smaller unit sizes of adhesives, and sealant or caulking compounds (in units of product, less packaging, which do not weigh more than 1 pound and do not consist of more than 16 fluid ounces) shall comply with statewide VOC standards and other requirements, including prohibitions on use of certain toxic compounds, of California Code of Regulations, Title 17, commencing with section 94504.5.				
4.504.2.2 <b>Paints and Coatings.</b> Architectural paints and coatings shall comply with VOC limits in Table 1 of the ARB Architectural Suggested Control Measure, as shown in Table 4.504.3, unless more stringent local limits apply. The VOC content limit for coatings that do not meet the definitions for the specialty coatings categories listed in Table 4.504.3 shall be determined by classifying the coating as a Flat, Nonflat or Nonflat-High Gloss coating, based on its gloss, as defined in subsections 4.21, 4.36, and 4.37 of the 2007 California Air Resources Board, Suggested Control Measure, and the corresponding Flat, Nonflat or Nonflat-High Gloss VOC limit in Table 4.504.3 shall apply.				
4.504.2.3 <b>Aerosol Paints and Coatings.</b> Aerosol paints and coatings shall meet the Product-weighted MIR limits for ROC in Section 94522(e)(2) and other requirements, including prohibitions on use of certain toxic compounds and ozone depleting substances, in Sections 94522(e)(1) and (f)(1) of California Code of Regulations, Title 17, commencing with Section 94520, and in areas under the jurisdiction of the Bay Area Air Quality Management District additionally comply with the percent VOC by weight of product limits of Regulation 8, Rule 49.				
4.504.2.4 <b>Verification.</b> Verification of compliance with this section shall be provided at the request of the enforcing agency. Documentation may include, but is not limited to, the following:				
1. Manufacturer's product specification. 2. Field verification of on-site product containers.				
<b>TABLE 4.504.1 - ADHESIVE VOC LIMIT<sub>1,2</sub></b> (Less Water and Less Exempt Compounds in Grams per Liter)				
<b>ARCHITECTURAL APPLICATIONS</b>	<b>VOC LIMIT</b>			
INDOOR CARPET ADHESIVES	50			
CARPET PAD ADHESIVES	50			
OUTDOOR CARPET ADHESIVES	150			
WOOD FLOORING ADHESIVES	100			
RUBBER FLOOR ADHESIVES	60			
SUBFLOOR ADHESIVES	50			
CERAMIC TILE ADHESIVES	65			
VCT & ASPHALT TILE ADHESIVES	50			
DRYWALL & PANEL ADHESIVES	50			
COVE BASE ADHESIVES	50			
MULTIPURPOSE CONSTRUCTION ADHESIVE	70			
STRUCTURAL GLAZING ADHESIVES	100			
SINGLE-PLY ROOF MEMBRANE ADHESIVES	250			
OTHER ADHESIVES NOT LISTED	50			
<b>SPECIALTY APPLICATIONS</b>				
PVC WELDING	510			
CPVC WELDING	490			
ABS WELDING	325			
PLASTIC CEMENT WELDING	250			
ADHESIVE PRIMER FOR PLASTIC	550			
CONTACT ADHESIVE	80			
SPECIAL PURPOSE CONTACT ADHESIVE	250			
STRUCTURAL WOOD MEMBER ADHESIVE	140			
TOP & TRIM ADHESIVE	250			
<b>SUBSTRATE SPECIFIC APPLICATIONS</b>				
METAL TO METAL	30			
PLASTIC FOAMS	50			
POROUS MATERIAL (EXCEPT WOOD)	50			
WOOD	30			
FIBERGLASS	80			
1. IF AN ADHESIVE IS USED TO BOND DISSIMILAR SUBSTRATES TOGETHER, THE ADHESIVE WITH THE HIGHEST VOC CONTENT SHALL BE ALLOWED.				
2. FOR ADDITIONAL INFORMATION REGARDING METHODS TO MEASURE THE VOC CONTENT SPECIFIED IN THIS TABLE, SEE SOUTH COAST AIR QUALITY MANAGEMENT DISTRICT RULE 1168.				

**TABLE 4.504.2 - SEALANT VOC LIMIT**  
(Less Water and Less Exempt Compounds in Grams per Liter)

SEALANTS	VOC LIMIT
ARCHITECTURAL	250
MARINE DECK	760
NONMEMBRANE ROOF	300
ROADWAY	250
SINGLE-PLY ROOF MEMBRANE	450
OTHER	420

**TABLE 4.504.3 - VOC CONTENT LIMITS FOR ARCHITECTURAL COATINGS<sub>3</sub>**  
(GRAMS OF VOC PER LITER OF COATING, LESS WATER & LESS EXEMPT COMPOUNDS)

COATING CATEGORY	VOC LIMIT
FLAT COATINGS	50
NON-FLAT COATINGS	100
NONFLAT-HIGH GLOSS COATINGS	150
SPECIALTY COATINGS	
ALUMINUM ROOF COATINGS	400
BASEMENT SPECIALTY COATINGS	400
BITUMINOUS ROOF COATINGS	50
BOND BREAKERS	350
CONCRETE CURING COMPOUNDS	350
CONCRETE/MASONRY SEALERS	100
DRIVEWAY SEALERS	50
DRY FOAM COATINGS	150
FAUX FINISHING COATINGS	350
FIRE RESISTIVE COATINGS	350
FLOOR COATINGS	100
FORM-RELEASE COMPOUNDS	250
GRAPHIC ARTS COATINGS (SIGN PAINTS)	500
HIGH TEMPERATURE COATINGS	420
INDUSTRIAL MAINTENANCE COATINGS	250
LOW SOLIDS COATINGS	120
MAGNESITE CEMENT COATINGS	450
MASTIC TEXTURE COATINGS	100
METALLIC PIGMENTED COATINGS	500
MULTICOLOR COATINGS	250
PRETREATMENT WASH PRIMERS	420
PRIMERS, SEALERS, & UNDERCOATERS	100
REACTIVE PENETRATING SEALERS	350
RECYCLED COATINGS	250
ROOF COATINGS	50
RUST PREVENTATIVE COATINGS	250
SHELLAC	
CLEAR	730
OPAQUE	550
SPECIALTY PRIMERS, SEALERS & UNDERCOATERS	100
STAINS	250
STONE CONSOLIDANTS	450
SWIMMING POOL COATINGS	340
TRAFFIC MARKING COATINGS	100
TUB & TILE REFINISH COATINGS	420
WATERPROOFING MEMBRANES	250
WOOD COATINGS	275
WOOD PRESERVATIVES	350
ZINC-RICH PRIMERS	340

1. GRAMS OF VOC PER LITER OF COATING, INCLUDING WATER & EXEMPT COMPOUNDS  
2. THE SPECIFIED LIMITS REMAIN IN EFFECT UNLESS REVISED LIMITS ARE LISTED IN SUBSEQUENT COLUMNS IN THE TABLE.  
3. VALUES IN THIS TABLE ARE DERIVED FROM THOSE SPECIFIED BY THE CALIFORNIA AIR RESOURCES BOARD, ARCHITECTURAL COATINGS SUGGESTED CONTROL MEASURE, FEB. 1, 2008. MORE INFORMATION IS AVAILABLE FROM THE AIR RESOURCES BOARD.

1. IF AN ADHESIVE IS USED TO BOND DISSIMILAR SUBSTRATES TOGETHER, THE ADHESIVE WITH THE HIGHEST VOC CONTENT SHALL BE ALLOWED.

2. FOR ADDITIONAL INFORMATION REGARDING METHODS TO MEASURE THE VOC CONTENT SPECIFIED IN THIS TABLE, SEE SOUTH COAST AIR QUALITY MANAGEMENT DISTRICT RULE 1168.

**TABLE 4.504.5 - FORMALDEHYDE LIMITS:**

PRODUCT	CURRENT LIMIT
HARDWOOD PLYWOOD VENEER CORE	0.05
HARDWOOD PLYWOOD COMPOSITE CORE	0.05
PARTICLE BOARD	0.09
MEDIUM DENSITY FIBERBOARD	0.11
THIN MEDIUM DENSITY FIBERBOARD	0.13

1. VALUES IN THIS TABLE ARE DERIVED FROM THOSE SPECIFIED BY THE CALIFORNIA AIR RESOURCES BOARD, AIR TOXICS CONTROL MEASURE FOR COMPOSITE WOOD AS TESTED IN ACCORDANCE WITH ASTM E 1333. FOR ADDITIONAL INFORMATION, SEE CALIFORNIA CODE OF REGULATIONS, TITLE 17, SECTIONS 93120 THROUGH 93124.
2. THIN MEDIUM DENSITY FIBERBOARD HAS A MAXIMUM THICKNESS OF 9/16" (14 MM).

#### DIVISION 4.5 ENVIRONMENTAL QUALITY (continued)

4.504.3 **CARPET**. All carpet installed in the building interior shall meet the requirements of the California Department of Public Health, "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers," Version 1.2, January 2017 (Emission testing method for California Specification 01350)

See California Department of Public Health's website for certification programs and testing labs.

<https://www.cdph.ca.gov/Programs/CCDPHP/DEODC/EHLB/IAQ/Pages/VOC.aspx>

4.504.3.1 **Carpet cushion.** All carpet cushion installed in the building interior shall meet the requirements of the California Department of Public Health, "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers," Version 1.2, January 2017 (Emission testing method for California Specification 01350)

See California Department of Public Health's website for certification programs and testing labs.

<https://www.cdph.ca.gov/Programs/CCDPHP/DEODC/EHLB/IAQ/Pages/VOC.aspx>

4.504.3.2 **Carpet adhesive.** All carpet adhesive shall meet the requirements of Table 4.504.1.

4.504.4 **RESILIENT FLOORING SYSTEMS.** Where resilient flooring is installed, at least 80% of floor area receiving resilient flooring shall meet the requirements of the California Department of Public Health, "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers," Version 1.2, January 2017 (Emission testing method for California Specification 01350)

See California Department of Public Health's website for certification programs and testing labs.

<https://www.cdph.ca.gov/Programs/CCDPHP/DEODC/EHLB/IAQ/Pages/VOC.aspx>

4.504.5 **COMPOSITE WOOD PRODUCTS.** Hardwood plywood, particleboard and medium density fiberboard composite wood products used on the interior or exterior of the buildings shall meet the requirements for formaldehyde as specified in ARB's Air Toxics Control Measure for Composite Wood (17 CCR 93120 et seq.).

by or before the dates specified in those sections, as shown in Table 4.504.5



DISCLAIMER: BY USING THESE STANDARD PLANS, THE USER AGREES TO RELEASE THE CITY OF HANFORD FROM ANY AND ALL CLAIMS, LIABILITIES, SUITS AND DEMANDS ON ACCOUNT OF ANY INJURY, DAMAGE, OR LOSS TO PERSONS OR PROPERTY, ARISING OUT OF THE USE OF THESE CONSTRUCTION DOCUMENTS. THE USE OF THESE PLANS DOES NOT ELIMINATE OR REDUCE THE USER'S RESPONSIBILITY TO VERIFY ANY AND ALL INFORMATION.



## REVISIONS

—	—	—
—	—	—
—	—	—
—	—	—
—	—	—

PROJECT TITLE	CITY OF HANFORD – PRE-REVIEWED ADU PROGRAM
AGENCY	City of Hanford

ADU SQFT	375
----------	-----

DRAWING SCALE	1/2" = 1'
---------------	-----------

CITY OF HANFORD	BUILDING DIVISION
-----------------	-------------------

APPROVED	1'
----------	----

THIS SET OF PLANS AND SPECIFICATIONS MUST BE KEPT ON THE JOB AT ALL TIMES AND NO CHANGES OR ALTERATIONS SHALL BE MADE EXCEPT BY THE BUILDING DIVISION.
--

THE STAMPING OF THIS PLAN AND SPECIFICATIONS SHALL NOT BE HELD TO PERMIT OR TO BE AN APPROVAL OF THE VIOLATION OF ANY PROVISIONS OF ANY CITY ORDINANCE OR STATE LAW, 'REVIEWED FOR CODE COMPLIANCE.'
--

By: Mitchell Coach
--------------------

12/11/2024
------------

**CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD** CFIR-PRF-01-E  
Project Name: Hanford Plan 375 ADU  
Calculation Date/Time: 2024-10-23T16:32:05-07:00  
Input File Name: Precision Engineering\_Hanford Plan 375 ADU.rbd22x  
(Page 4 of 12)

**ENERGY USE SUMMARY**

Energy Use	Standard Design Source Energy (E0R1) (kBtu/H <sup>2</sup> ·yr)	Standard Design TDV Energy (E0R2) (kWh/H <sup>2</sup> ·yr)	Proposed Design Source Energy (E0R1) (kBtu/H <sup>2</sup> ·yr)	Proposed Design TDV Energy (E0R2) (kWh/H <sup>2</sup> ·yr)	Compliance Margin (E0R1)	Compliance Margin (E0R2)
Space Heating	1.26	9.35	1.31	9.83	-0.05	-0.48
Space Cooling	3.96	75.9	3.83	73.32	0.13	2.58
IAQ Ventilation	0.54	5.74	0.54	5.74	0	0
Water Heating	17.85	75.29	16.08	68.15	1.77	7.14
Self Utilization/Resiliency Credit		0	0	0	0	0
South Facing Efficiency Compliance Total	23.61	166.28	21.76	157.04	1.85	9.24
Space Heating	1.26	9.35	1.31	9.76	-0.05	-0.41
Space Cooling	3.96	75.9	4.07	79.02	-0.11	-3.12
IAQ Ventilation	0.54	5.74	0.54	5.74	0	0
Water Heating	17.85	75.29	16.08	68.15	1.77	7.14
Self Utilization/Resiliency Credit		0	0	0	0	0
East Facing Efficiency Compliance Total	23.61	166.28	22	162.67	1.61	3.61

**CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD** CFIR-PRF-01-E  
Project Name: Hanford Plan 375 ADU  
Calculation Date/Time: 2024-10-23T16:32:05-07:00  
Input File Name: Precision Engineering\_Hanford Plan 375 ADU.rbd22x  
(Page 5 of 12)

**ENERGY DESIGN RATINGS**

Energy Use	Energy Design Ratings			Compliance Margins		
	Source Energy (E0R1)	Efficiency <sup>2</sup> (E0R2)	Total <sup>3</sup> (E0R3)	Source Energy (E0R1)	Efficiency <sup>2</sup> (E0R2)	Total <sup>3</sup> (E0R3)
Standard Design	54.3	47.5	36.4	Proposed Design		
North Facing	51.9	44.9	34.8	2.4	2.6	1.6
East Facing	52.2	46.5	35.7	2.1	1	0.7
South Facing	51.8	44.6	34.7	2.5	2.9	1.7
West Facing	52.4	47.4	36.2	1.9	0.1	0.2

**CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD** CFIR-PRF-01-E  
Project Name: Hanford Plan 375 ADU  
Calculation Date/Time: 2024-10-23T16:32:05-07:00  
Input File Name: Precision Engineering\_Hanford Plan 375 ADU.rbd22x  
(Page 6 of 12)

**ENERGY USE SUMMARY**

Energy Use	Standard Design Source Energy (E0R1) (kBtu/H <sup>2</sup> ·yr)	Standard Design TDV Energy (E0R2) (kWh/H <sup>2</sup> ·yr)	Proposed Design Source Energy (E0R1) (kBtu/H <sup>2</sup> ·yr)	Proposed Design TDV Energy (E0R2) (kWh/H <sup>2</sup> ·yr)	Compliance Margin (E0R1)	Compliance Margin (E0R2)
Space Heating	1.26	9.35	1.31	9.76	-0.05	-0.41
Space Cooling	3.96	75.9	4.07	79.02	-0.11	-3.12
IAQ Ventilation	0.54	5.74	0.54	5.74	0	0
Water Heating	17.85	75.29	16.08	68.15	1.77	7.14
Self Utilization/Resiliency Credit		0	0	0	0	0
South Facing Efficiency Compliance Total	23.61	166.28	21.76	157.04	1.85	9.24
Space Heating	1.26	9.35	1.31	9.76	-0.05	-0.41
Space Cooling	3.96	75.9	4.16	81.97	-0.2	-6.07
IAQ Ventilation	0.54	5.74	0.54	5.74	0	0
Water Heating	17.85	75.29	16.08	68.15	1.77	7.14
Self Utilization/Resiliency Credit		0	0	0	0	0
East Facing Efficiency Compliance Total	23.61	166.28	22	162.67	1.61	3.61

**CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD** CFIR-PRF-01-E  
Project Name: Hanford Plan 375 ADU  
Calculation Date/Time: 2024-10-23T16:32:05-07:00  
Input File Name: Precision Engineering\_Hanford Plan 375 ADU.rbd22x  
(Page 7 of 12)

**OVERHANGS AND FINS**

01	02	03	04	05	06	07	08	09	10	11	12	13	14
Front Wall	White House	R21 Wall + R5		Attic	Orient	Azimuth	Gross Area (H <sup>2</sup> )	Window and Door Area (H2)	YR (deg)				
Left Wall	White House	R21 Wall + R5	90		Front	0	0	0	90				
Right Wall	White House	R21 Wall + R5	180		Back	200	32	90					
Attic Roof	White House	R21 Wall + R5	270		Right	120	0	90					
						n/a	375	n/a					

**CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD** CFIR-PRF-01-E  
Project Name: Hanford Plan 375 ADU  
Calculation Date/Time: 2024-10-23T16:32:05-07:00  
Input File Name: Precision Engineering\_Hanford Plan 375 ADU.rbd22x  
(Page 8 of 12)

**SLAB FLOORS**

01	02	03	04	05	06	07	08	09	10	11	12	13	14
Name	Zone	Area (H <sup>2</sup> )	Perimeter (ft)	Edge Insul. R-value									
Slab Floor	Whole House	375	80	n/a									

**CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD** CFIR-PRF-01-E  
Project Name: Hanford Plan 375 ADU  
Calculation Date/Time: 2024-10-23T16:32:05-07:00  
Input File Name: Precision Engineering\_Hanford Plan 375 ADU.rbd22x  
(Page 9 of 12)

**OPAQUE SURFACES**

01	02	03	04	05	06	07	08	09	10	11	12	13	14
Name	Zone	Construction	Orientation	Azimuth	Width (ft)	Height (ft)	Multi. (ft <sup>2</sup> )	U-factor	SHGC	SHGC Source	External Shading		
W01 3030 XD	Window	Front Wall	Front	0	3	3	1	0.3	NFRC	Bug Screen			
W02 4040 XD	Window	Front Wall	Front	0	4	4	1	0.3	NFRC	Bug Screen			
W03 3030 XD	Window	Back Wall	Back	180	3	3	1	0.3	NFRC	Bug Screen			
W04 3030 XD	Window	Back Wall	Back	180	3	1	3	0.3	NFRC	Bug Screen			

**CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD** CFIR-PRF-01-E  
Project Name: Hanford Plan 375 ADU  
Calculation Date/Time: 2024-10-23T16:32:05-07:00  
Input File Name: Precision Engineering\_Hanford Plan 375 ADU.rbd22x  
(Page 10 of 12)

**WATER INSULATION / FROST PROTECTION**

01	02	03	04	05	06	07	08	09	10	11	12	13	14
Name	Zone Type	HVAC System Name	Zone Floor Area (H <sup>2</sup> )	Avg. Ceiling Height	Water Heating System 1	Status							
Whole House	Conditioned	Res HVAC1	375	8	DHW Sys 1	New							

**CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD** CFIR-PRF-01-E  
Project Name: Hanford Plan 375 ADU  
Calculation Date/Time: 2024-10-23T16:32:05-07:00  
Input File Name: Precision Engineering\_Hanford Plan 375 ADU.rbd22x  
(Page 11 of 12)

**WATER HEAT PUMPS**

01	02	03	04	05	06	07	08	09	10	11	12	13
Name	System Type	Tank Type	# of Units	Tank Vol. (gal)	Heating Efficiency Type	Rated Input Type	Input Power or Pilot	Tank Location	Standby Loss or Recovery Eff	Set Hr Rating or Flow or Rate	Tank Location	
OHW Header 1	Gas	Consumer Instantaneou	1	0	UEF	0.93	Btu/hr	200000	0	n/a	n/a	